

Tazewell County Highway Department

AUTHORIZATION TO BID FORM

Addenda will be published to our Bid Letting page in the same manner as the plans and specifications. It is the sole responsibility of the plan holders to periodically check the website for plan addenda.

ALL BIDDERS PLANNING TO PLACE A BID MUST FILL OUT THIS FORM TO BE AUTHORIZED TO BID.

- This form must be completed, signed and either faxed to (309) 925-5533 or emailed to jsciortino@tazewell-il.gov.
- Failure to submit this completed form will result in the bid not being accepted.
- Contractors may verify we have received their Authorization to Bid form by checking the **Plan Holders List** found under the corresponding letting date.
- If an email address is provided, a Notice of Addenda will be sent when updates are available.
- Bid results are typically posted by noon on the day of the letting and are preliminary until approved by the County Board on the last Wednesday of the month.

Company Name:	
Address:	
Addiess.	
Phone:	
Fax:	
Email:	
Bid Letting Date:	

Projects Intending to Bid on:

Section Number:	Description:



Local Public Agency Formal Contract Proposal

COVER	SHEET		
Proposal Submitted By:			
Contractor's Name	1		
Contractor's Address	City		State Zip Code
STATE OF ILLINOIS			
Local Public Agency		County	Section Number
Morton Road District		Tazewell	24-14000-01-GM
Route(s) (Street/Road Name)			Type of Funds
TR156-A / Hires Trace			MFT and RBI Funds
Proposal Only Proposal and Plans Proposal only, plans	are separa	te	
Submitted/Approved For Local Public Agency:			
For a County and Road District Project		For a M	unicinal Project
For a County and Road District Project		For a M	unicipal Project
For a County and Road District Project Submitted/Approved			unicipal Project
Submitted/Approved Highway Commissioner Signature & Date	Signatu		
Submitted/Approved		Submitted re & Date	
Submitted/Approved Highway Commissioner Signature & Date Darrell Moore Date: 2024.03.06 09:51:15 -06'00'	Signatu	Submitted re & Date	
Submitted/Approved Highway Commissioner Signature & Date Digitally signed by Darrell Moore Date: 2024.03.06 09:51:15 -06'00' Submitted/Approved		Submitted re & Date	
Submitted/Approved Highway Commissioner Signature & Date Darrell Moore Date: 2024.03.06 09:51:15 -06'00' Submitted/Approved County Engineer/Superintendent of Highways Signature & Date Digitally signed by Dan Parr		Submitted re & Date	
Submitted/Approved Highway Commissioner Signature & Date Darrell Moore Date: 2024.03.06 09:51:15 -06'00' Submitted/Approved County Engineer/Superintendent of Highways Signature & Date Dan Parr Date: 2024.03.06 09:51:43		Submitted re & Date Title	
Submitted/Approved Highway Commissioner Signature & Date Darrell Moore Date: 2024.03.06 09:51:15 -06'00' Submitted/Approved County Engineer/Superintendent of Highways Signature & Date Digitally signed by Dan Parr		Submitted re & Date Title Departmen	nt of Transportation
Submitted/Approved Highway Commissioner Signature & Date Darrell Moore Date: 2024.03.06 09:51:15 -06'00' Submitted/Approved County Engineer/Superintendent of Highways Signature & Date Dan Parr Date: 2024.03.06 09:51:43	Official	Submitted re & Date Title Departmen	nt of Transportation d based on limited review

Note: All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed.

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
Morton Road District	Tazewell	24-14000-01-GM	TR156-A / Hires Trace

	NOTICE TO BIDDERS		
Sealed proposals for the project de	escribed below will be received at the office of T	he Tazewell County Engi	neer
	_	Name of Of	fice
21308 Illinois Route 9	Tremont, Illinois 61568	until 1:30 PM	on 04/15/24
	Address	Time	Date
Sealed proposals will be opened a	and read publicly at the office of The Tazewell	County Engineer	
	·	Name of Office	
21308 Illinois Route 9	Tremont, Illinois 61568	at 1:30 PM	on 04/15/24
	Address	Time	Date

DESCRIPTION OF WORK

Location	Project Length
TR 156A / Hires Trace	1,635 LF

Proposed Improvement

HMA SURF REM BUTT JT, HMA SURF REM 1 1/2, HMA SC IL-9.5 C N50 and related work

1. Plans and proposal forms will be available in the office of

Tazewell County Highway Engineer

21308 Illinois Route 9

Tremont IL,61568

2. Prequalification

If checked, the 2 apparent as read low bidders must file within 24 hours after the letting an "Affidavit of Availability" (Form BC 57) in triplicate, showing all uncompleted contracts awarded to them and all low bids pending award for Federal, State, County, Municipal and private work. One original shall be filed with the Awarding Authority and two originals with the IDOT District Office.

- 3. The Awarding Authority reserves the right to waive technicalities and to reject any or all proposals as provided in BLRS Special Provision for Bidding Requirements and Conditions for Contract Proposals.
- 4. The following BLR Forms shall be returned by the bidder to the Awarding Authority:
 - a. Local Public Agency Formal Contract Proposal (BLR 12200)
 - b. Schedule of Prices (BLR 12201)
 - c. Proposal Bid Bond (BLR 12230) (if applicable)
 - d. Apprenticeship or Training Program Certification (BLR 12325) (do not use for project with Federal funds.)
 - e. Affidavit of Illinois Business Office (BLR 12326) (do not use for project with Federal funds)
- 5. The quantities appearing in the bid schedule are approximate and are prepared for the comparison of bids. Payment to the Contractor will be made only for the actual quantities of work performed and accepted or materials furnished according to the contract. The scheduled quantities of work to be done and materials to be furnished may be increased, decreased or omitted as hereinafter provided.
- 6. Submission of a bid shall be conclusive assurance and warranty the bidder has examined the plans and understands all requirements for the performance of work. The bidder will be responsible for all errors in the proposal resulting from failure or neglect to conduct an in depth examination. The Awarding Authority will, in no case, be responsible for any costs, expenses, losses or changes in anticipated profits resulting from such failure or neglect of the bidder.
- 7. The bidder shall take no advantage of any error or omission in the proposal and advertised contract.
- 8. If a special envelope is supplied by the Awarding Authority, each proposal should be submitted in that envelope furnished by the Awarding Agency and the blank spaces on the envelope shall be filled in correctly to clearly indicate its contents. When an envelope other than the special one furnished by the Awarding Authority is used, it shall be marked to clearly indicate its contents. When sent by mail, the sealed proposal shall be addressed to the Awarding Authority at the address and in care of the official in whose office the bids are to be received. All proposals shall be filed prior to the time and at the place specified in the Notice to Bidders. Proposals received after the time specified will be returned to the bidder unopened.
- 9. Permission will be given to a bidder to withdraw a proposal if the bidder makes the request in writing or in person before the time for opening proposals.

Lo	ocal Public Agency	County	Section Number	Route(s) (Street/Road Name)
M	orton Road District	Tazewell	24-14000-01-GM	TR156-A / Hires Trace
			PROPOSAL	
1.	Proposal of			
			Contractor's Name	
		Co	ontractor's Address	
2.	The plans for the proposed wor	k are those prepared by th	e Tazewell County Highway	Department
	and approved by the Departme	nt of Transportation on Ma	ar 13, 2024	
3.		ridge Construction" and the	by the Department of Transportation " Supplemental Specifications an	on and designated as "Standard d Recurring Special Provisions" thereto,
4.	The undersigned agrees to acc Recurring Special Provisions"			s indicated on the "Check Sheet for
5.	The undersigned agrees to cor is granted in accordance with t		working days or by 09	9/01/24 unless additional time
6.		ond is not required, the prop secute a contract and contra	posal guaranty check will be held i	eposit a contract bond for the full amount or n lieu thereof. If this proposal is accepted agreed that the Bid Bond of check shall be
7.	the unit price multiplied by the	quantity, the unit price shall	Il govern. İf a unit price is omitted	e is a discrepancy between the products of , the total price will be divided by the nit price nor a total price is shown.
8.	The undersigned submits here	with the schedule of prices	on BLR 12201 covering the work	to be performed under this contract.
9.				e combinations on BLR 12201, the work I specified in the Schedule for Multiple Bids
10.	. A proposal guaranty in the pro	oper amount, as specified ir	n BLRS Special Provision for Bidd	ing Requirements and Conditions for
	Contract Proposals, will be req	quired. Bid Bonds Will	be allowed as a proposal gua	ranty. Accompanying this proposal is either
	-			lying with the specifications, made payable
			Treasurer of Tazewell County	
	The amount of the check is			()
		Attach Cashier's	Check or Certified Check Here	
		es which would be required	for each individual bid proposal. I	als, the amount must be equal to the f the proposal guaranty check is
	The proposal guaranty check	will be found in the bid pro	posal for: Section Number	·

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
Morton Road District	Tazewell	24-14000-01-GM	TR156-A / Hires Trace

CONTRACTOR CERTIFICATIONS

The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder.

- 1. **Debt Delinquency.** The bidder or contractor or subcontractor, respectively, certifies that it is not delinquent in the payment of any tax administered by the Department of Revenue unless the individual or other entity is contesting, in accordance with the procedure established by the appropriate Revenue Act, its liability for the tax or the amount of the tax. Making a false statement voids the contract and allows the Department to recover all amounts paid to the individual or entity under the contract in a civil action.
- 2. **Bid-Rigging or Bid Rotating**. The bidder or contractor or subcontractor, respectively, certifies that it is not barred from contracting with the Department by reason of a violation of either 720 ILCS 5/33E-3 or 720 ILCS 5/33E-4.

A violation of section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense, or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent on behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State of Local government. No corporation shall be barred from contracting with any unit of State or Local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent on behalf of the corporation.

- 3. **Bribery.** The bidder or contractor or subcontractor, respectively, certifies that, it has not been convicted of bribery or attempting to bribe an officer or employee of the State of Illinois or any unit of local government, nor has the firm made an admission of guilt of such conduct which is a matter or record, nor has an official, agent, or employee of the firm committed bribery or attempted bribery on behalf of the firm and pursuant to the direction or authorization of a responsible official of the firm.
- 4. **Interim Suspension or Suspension.** The bidder or contractor or subcontractor, respectively, certifies that it is not currently under a suspension as defined in Subpart I of Title 44 Subtitle A Chapter III Part 6 of the Illinois Administrative code. Furthermore, if suspended prior to completion of this work, the contract or contracts executed for the completion of this work may be canceled.

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
Morton Road District	Tazewell	24-14000-01-GM	TR156-A / Hires Trace
		SIGNATURES	
(If an individual)		Bidder Signature & Date	
		Business Address	
		O'A.	Ohada Zin Oada
		City	State Zip Code
(If a partnership)		Firm Name	
		0: 4 0 0 4	
		Signature & Date	
		Title	
		Business Address	
		City	State Zip Code
Insert the Names and Address	ses of all Partners		
(If a corporation)		Corporate Name	
(ii a corporation)			
		Signature & Date	
		Title	
		Puoiness Address	
		Business Address	
		City	State Zip Code
		-	
	Insert Names of Officers	President	

	Secretary
Attest:	
	Treasurer
Secretary	



Schedule of Prices



Contractor's Name			
Contractor's Address	City		State Zip Code
Local Public Agency		County	Section Number
Morton Road District		Tazewell	24-14000-01-GM
Route(s) (Street/Road Name)			
TR156A / Hires Trace			
	Schedule for Multiple B	ids	
Combination Letter	Section Included in Com	binations	Total

Schedule for Single Bid

(For complete information covering these items, see plans and specifications.)

Item Number	Items	Unit	Quantity	Unit Price	Total
1	HMA SURF REM BUTT JOINT	SQ YD	140		
2	HMA SURF REM 1 1/2	SQ YD	4,623		
3	TEMPORARY RAMP	SQ YD	22		
4	P BIT MATLS TACK CT	POUND	4,395		
6	HMA SC IL-9.5 C N50	TON	513		
7	TRAF CONT & PROT SPL	L SUM	1		
		1	Bi	dder's Total Proposal	

- 1. Each pay item should have a unit price and a total price.
- 2. If no total price is shown or if there is a discrepancy between the product of the unit price multiplied by the quantity, the unit price shall govern.
- 3. If a unit price is omitted, the total price will be divided by the quantity in order to establish a unit price.
- 4. A bid may be declared unacceptable if neither a unit price or total price is shown.



Local Public Agency Proposal Bid Bond

Local Public Agency		County	Section Number
Morton Road District		Tazewell	24-14000-01-GM
WE,			as PRINCIPAL, and
			as SURETY, are held jointly,
severally and firmly bound unto the above Local Public Agency (her price, or for the amount specified in the proposal documents in effe bind ourselves, our heirs, executors, administrators, successors, ar instrument.	ct on the date	e of invitation for bid	he penal sum of 5% of the total bid ds, whichever is the lesser sum. We
WHEREAS THE CONDITION OF THE FOREGOING OBL	IGATION IS	SUCH that, the sai	id PRINCIPAL is submitting a written
proposal to the LPA acting through its awarding authority for the co THEREFORE if the proposal is accepted and a contract a and the PRINCIPAL shall within fifteen (15) days after award enter performance of the work, and furnish evidence of the required insur and Bridge Construction" and applicable Supplemental Specificatio full force and effect.	nstruction of warded to the into a formal ance covera	the work designate PRINCIPAL by the contract, furnish su ge, all as provided	ed as the above section. e LPA for the above designated section urety guaranteeing the faithful in the "Standard Specifications for Road"
IN THE EVENT the LPA determines the PRINCIPAL has f	ailed to enter	into a formal contr	act in compliance with any
requirements set forth in the preceding paragraph, then the LPA ac recover the full penal sum set out above, together with all court cos IN TESTIMONY WHEREOF, the said PRINCIPAL ar	ts, all attorne	y fees, and any oth	ner expense of recovery.
respective officers this of			
Day Month and Year			
	incipal	mpany Name	
Company Name	Col	прапу маше	
Signature & Date	Sig	nature & Date	
By:	By:		
	<i>- - - - - - - - - -</i>		
Title	Title	e	
(If Principal is a joint venture of two or more contractors, the compa	ny names, ar	nd authorized signa	atures of each contractor must be
affixed.)	Surety		
Name of Surety	-	nature of Attornev-	in-Fact Signature & Date
	By:	,	J .
STATE OF IL			
COUNTY OF			
1	a Notary Pul	olic in and for said	county do hereby certify that
(Insert names of individuals signin	g on behalf of	PRINCIPAL & SURF	TY)
who are each personally known to me to be the same persons who PRINCIPAL and SURETY, appeared before me this day in person instruments as their free and voluntary act for the uses and purpose	se names are and acknowle	e subscribed to the edged respectively,	foregoing instrument on behalf of
Given under my hand and notarial seal this day	of		
Day	Mon	th and Year	
		Notary Public	Signature & Date
(SEAL, if required by the LPA)			
		Date com	mission expires

Local Public Agency	County	Section Number
Morton Road District	Tazewell	24-14000-01-GM
Ε	CTRONIC BID BOND	
☐ Electronic bid bond is allowed (box must be check	by LPA if electronic bid bond	is allowed)
electronic bid bond ID code and signing below, the Princip Principal and Surety are firmly bound unto the LPA under of two or more contractors, an electronic bid bond ID code venture.) Electronic Bid Bond ID Code	conditions of the bid bond as sl	nown above. (If PRINCIPAL is a joint venture ate must be affixed for each contractor in the
Liectionic Bid Bond 15 Code	Company/Bidde	i Name
	Signature & Dat	e



Affidavit of Availability

For the Letting of 04/15/24

Bureau of Construction 2300 South Dirksen Parkway/Room 322 Springfield, IL 62764 Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

Part I. Work Under Contract

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

	1	2	3	4	Awards Pending	Accumulated Totals
Contract Number						
Contract With						
Estimated Completion Date						
Total Contract Price						
Uncompleted Dollar Value if Firm is the Prime Contractor						
Uncompleted Dollar Value if Firm is the Subcontractor						
Total Value of All Work						

Part II. Awards Pending and Uncompleted Work to be done with your own forces.

List below the uncompleted dollar value of work for each contract and awards pending to be completed with your own forces. All work subcontracted to others will be listed on the reverse of this form. In a joint venture, list only that portion of the work to be done by your company. If no work is contracted, show NONE.

I, SHOW INCINE.			

Disclosure of this information is REQUIRED to accomplish the statutory purpose as outlined in the "Illinois Procurement Code." Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

Subcontractor Type of Work Subcontract Price Amount Uncompleted Subcontractor Type of Work		2	3		Awards Pending
Subcontract Price Amount Uncompleted Subcontractor					
Amount Uncompleted Subcontractor					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					1
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Total Uncompleted					
Notary					
I, being duly sworn, do hereby of undersigned for Federal, State, rejected and ALL estimated con	County, City and p				
Officer or Director			Subscrib	ed and sworn to before ı	
Title			ulis	day of	
Signature		Date			
				(Signature of Notary I	oublic)
			My comr	nission expires	
Company					
Company					
Address					
Address					
City	State	Zip Code			
				(Notary Seal)	
				(,,	

Part III. Work Subcontracted to Others.

Add pages for additional contracts

Printed 03/06/24 Page 2 of 2 BC 57 (Rev. 02/16/21)



Apprenticeship and Training Program Certification

Local Public Agency	County	Street Name/Road Name	Section Number				
Morton Road District	Tazewell	TR 156-A Hires Trace	24-14000-01-GM				
All contractors are required to complete the following certification For this contract proposal or for all bidding groups in this deliver and install proposal. For the following deliver and install bidding groups in this material proposal.							
Illinois Department of Transportation policy, adopte to be awarded to the lowest responsive and responsibility factors, this contract or departicipation in apprenticeship or training programs. Bureau of Apprenticeship and Training, and (2) appare required to complete the following certification.	nsible bidder. The aveliver and install propes that are (1) approves that are to the work of	ward decision is subject to approval osal requires all bidders and all bidd ed by and registered with the United	by the Department. In addition ler's subcontractors to disclose States Department of Labor's				
1. Except as provided in paragraph 4 below, the ungroup program, in an approved apprenticeship or this own employees.							
2. The undersigned bidder further certifies, for wo time of such bid, participating in an approved, app performance of work pursuant to this contract, estawork of the subcontract.	licable apprenticeship	o or training program; or (B) will, pric	r to commencement of				
3. The undersigned bidder, by inclusion in the list Certificate of Registration for all of the types of wo employees. Types of work or craft that will be subdany type of work or craft job category for which the	rk or crafts in which to contracted shall be in	he bidder is a participant and that wi cluded and listed as subcontract wo	II be performed with the bidder's rk. The list shall also indicate				
4. Except for any work identified above, if any bidd install proposal solely by individual owners, partne would be required, check the following box, and id	rs or members and n	ot by employees to whom the payme	ent of pre <u>va</u> iling rates of wages				
The requirements of this certification and disclosur provision to be included in all approved subcontrace each type of work or craft job category that will be afterward may require the production of a copy of Labor evidencing such participation by the contract shall not be necessary that any applicable program employment during the performance of the work of	cts. The bidder is res utilized on the project each applicable Certictor and any or all of in the sponsor be currently	sponsible for making a complete report is accounted for and listed. The Difficate of Registration issued by the lots subcontractors. In order to fulfill the young or that it will take application	ort and shall make certain that epartment at any time before or Jnited States Department of he participation requirement, it				
Bidder		Signature & Date					
Title							
Address		City	State Zip Code				
7.444.555		,,					



Affidavit of Illinois Business Office

I. Name of Affiant	Local Public Agency	County	Street Name/Road Name	Section Number
Name of Affliant being first duly sworn upon oath, state as follows: 1. That I am the	Morton Road District	Tazewell	TR 156-A Hires Trace	24-14000-01-GM
Name of Affliant being first duly sworn upon oath, state as follows: 1. That I am the		of		
being first duly sworn upon oath, state as follows: 1. That I am the	Name of Afficial	01	City of Afficant	Ctata of Afficant
1. That I am the		nws.	City of Amant	State of Amant
Office ro Position 2. That I have personal knowledge of the facts herein stated. 3. That, if selected under the proposal described above,	being met day ewent apen eath, state as lone	, wo.		
Office ro Position 2. That I have personal knowledge of the facts herein stated. 3. That, if selected under the proposal described above,	1 That I am the	of		
2. That I have personal knowledge of the facts herein stated. 3. That, if selected under the proposal described above,			Bidder	<u> </u>
State of Illinois, which will be located in				
State of Illinois, which will be located in	3. That, if selected under the proposal describ	ped above,		maintain a business office in the
County 4. That this business office will serve as the primary place of employment for any persons employed in the construction contemplated by this proposal. 5. That this Affidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code. Signature & Date				
4. That this business office will serve as the primary place of employment for any persons employed in the construction contemplated by this proposal. 5. That this Affidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code. Signature & Date	State of Illinois, which will be located in		County, Illinois.	
this proposal. 5. That this Affidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code. Signature & Date	4. T. 1.0: 1 :	•		
Notary Public State of IL County by Signed (or subscribed or attested) before me on by (date), authorized agent(s) of (name/s of person/s) Bidder Notary Public Signature & Date	4. That this business office will serve as the p this proposal.	rimary place of employ	ment for any persons employed in the	construction contemplated by
Notary Public State of IL County by Signed (or subscribed or attested) before me on by, authorized agent(s) of (name/s of person/s) Bidder Notary Public Signature & Date	5. That this Affidavit is given as a requiremen	t of state law as provide	ed in Section 30-22(8) of the Illinois Pr	rocurement Code.
Notary Public State of IL County by Signed (or subscribed or attested) before me on by, authorized agent(s) of (name/s of person/s) Bidder Notary Public Signature & Date			Signature & Date	
Notary Public State of IL County Signed (or subscribed or attested) before me on by (date) (name/s of person/s) Bidder Notary Public Signature & Date			oignature a Bate	
Notary Public State of IL County Signed (or subscribed or attested) before me on by (date) (name/s of person/s) Bidder Notary Public Signature & Date				
Notary Public State of IL County Signed (or subscribed or attested) before me on by (date) (name/s of person/s) Bidder Notary Public Signature & Date				
State of IL County Signed (or subscribed or attested) before me on by, authorized agent(s) of [name/s of person/s] Bidder Notary Public Signature & Date			Print Name of Affiant	
State of IL County Signed (or subscribed or attested) before me on by, authorized agent(s) of [name/s of person/s] Bidder Notary Public Signature & Date				
State of IL County Signed (or subscribed or attested) before me on by, authorized agent(s) of [name/s of person/s] Bidder Notary Public Signature & Date				
State of IL County Signed (or subscribed or attested) before me on by, authorized agent(s) of [name/s of person/s] Bidder Notary Public Signature & Date				
State of IL County Signed (or subscribed or attested) before me on by, authorized agent(s) of [name/s of person/s] Bidder Notary Public Signature & Date				
County Signed (or subscribed or attested) before me on by, authorized agent(s) of, authorized agent(s) of Bidder Notary Public Signature & Date	Notary Public			
Signed (or subscribed or attested) before me on by, authorized agent(s) of (date)	State of IL			
Signed (or subscribed or attested) before me on by, authorized agent(s) of (date)	County			
(date) , authorized agent(s) of (name/s of person/s) Bidder Notary Public Signature & Date	·			
, authorized agent(s) of	Signed (or subscribed or attested) before me		by	
(name/s of person/s) Bidder Notary Public Signature & Date		(date)		
Bidder Notary Public Signature & Date				, authorized agent(s) of
Notary Public Signature & Date		(name/s of person/s)		
Notary Public Signature & Date				
	Bidder			
			Notary Public Signa	ture & Date
My commission expires			Treating Training Original	
My commission expires				
My commission expires				
(SFAL)	(SEAL)		My commission expir	res

INDEX FOR SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS

Adopted January 1, 2024

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS and frequently used RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction

(Adopted 1-1-22) (Revised 1-1-24)

SUPPLEMENTAL SPECIFICATIONS

Std. Spe	<u>ec. Sec.</u>	<u>Page No.</u>
202	Earth and Rock Excavation	
204	Borrow and Furnished Excavation	
207	Porous Granular Embankment	3
211	Topsoil and Compost	4
407	Hot-Mix Asphalt Pavement (Full-Depth)	5
420	Portland Cement Concrete Pavement	6
502	Excavation for Structures	7
509	Metal Railings	8
540	Box Culverts	9
542	Pipe Culverts	
586	Granular Backfill for Structures	
630	Steel Plate Beam Guardrail	
644	High Tension Cable Median Barrier	36
665	Woven Wire Fence	37
782	Reflectors	
801	Electrical Requirements	40
821	Roadway Luminaires	43
1003	Fine Aggregates	44
1004	Coarse Aggregates	45
1010	Finely Divided Minerals	
1020	Portland Cement Concrete	47
1030	Hot-Mix Asphalt	
1061	Waterproofing Membrane System	
1067	Luminaire	50
1097	Reflectors	57



31

32

Check Sheet for Recurring Special Provisions

150

151

Local Public A	Agency		County	Section Number
Morton Roa	ad Distri	et	Tazewell	24-14000-01-GM
Check thi	is box for	lettings prior to 01/01/2024.		
		g Special Provisions Indicated By An "X" Are Applicable T	o This Contract And Are	e Included By Reference:
	,	Recurring Special Provisio		,
Chec	ck Sheet#		<u>.</u>	Page No.
1		Additional State Requirements for Federal-Aid Construc	tion Contracts	59
2		Subletting of Contracts (Federal-Aid Contracts)		62
3		EEO		63
4		Specific EEO Responsibilities Non Federal-Aid Contract	ts	73
5		Required Provisions - State Contracts		78
6		Asbestos Bearing Pad Removal		84
7		Asbestos Waterproofing Membrane and Asbestos HMA	Surface Removal	85
8		Temporary Stream Crossings and In-Stream Work Pads	3	86
9		Construction Layout Stakes		87
10		Use of Geotextile Fabric for Railroad Crossing		90
11		Subsealing of Concrete Pavements		92
12		Hot-Mix Asphalt Surface Correction		96
13		Pavement and Shoulder Resurfacing		98
14		Patching with Hot-Mix Asphalt Overlay Removal		99
15		Polymer Concrete		101
16		Reserved		103
17		Bicycle Racks		104
18		Temporary Portable Bridge Traffic Signals		106
19		Nighttime Inspection of Roadway Lighting		108
20		English Substitution of Metric Bolts		109
21		Calcium Chloride Accelerator for Portland Cement Cond	crete	110
22		Quality Control of Concrete Mixtures at the Plant		111
23		Quality Control/Quality Assurance of Concrete Mixtures		119
24		Reserved		135
25		Reserved		136
26		Temporary Raised Pavement Markers		137
27		Restoring Bridge Approach Pavements Using High-Den	sity Foam	138
28		Portland Cement Concrete Inlay or Overlay		141
29		Portland Cement Concrete Partial Depth Hot-Mix Aspha	alt Patching	145
30		Longitudinal Joint and Crack Patching		148

Concrete Mix Design - Department Provided

Station Numbers in Pavements or Overlays

 Local Public Agency
 County
 Section Number

 Morton Road District
 Tazewell
 24-14000-01-GM

The Following Local Roads And Streets Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Local Roads And Streets Recurring Special Provisions

<u>Check</u>	Sheet #	#	<u>Page No.</u>
LRS 1		Reserved	153
LRS 2		Furnished Excavation	154
LRS 3	\boxtimes	Work Zone Traffic Control Surveillance	155
LRS 4	\boxtimes	Flaggers in Work Zones	156
LRS 5	\boxtimes	Contract Claims	157
LRS 6	\boxtimes	Bidding Requirements and Conditions for Contract Proposals	158
LRS 7		Bidding Requirements and Conditions for Material Proposals	164
LRS 8		Reserved	170
LRS 9		Bituminous Surface Treatments	171
LRS 10		Reserved	175
LRS 11	\boxtimes	Employment Practices	176
LRS 12	\boxtimes	Wages of Employees on Public Works	178
LRS 13	\boxtimes	Selection of Labor	180
LRS 14		Paving Brick and Concrete Paver Pavements and Sidewalks	181
LRS 15	\boxtimes	Partial Payments	184
LRS 16		Protests on Local Lettings	185
LRS 17	\boxtimes	Substance Abuse Prevention Program	186
LRS 18		Multigrade Cold Mix Asphalt	187
LRS 19		Reflective Crack Control Treatment	188

TABLE OF CONTENTS

Page 1	Bidding Requirements and Conditions
	Description of Work
	Traffic
	Traffic Control Plan
	Substitution of Bituminous Mixtures
Page 2	Hot-Mix Asphalt Surface Removal- Butt Joint
	Hot-Mix Asphalt Surface Removal
Page 3	Hot-Mix Asphalt Surface Removal (Cont'd.)
Page 4	Hot-Mix Asphalt Surface Removal (Cont'd.)
	Weight Limits
	General Notes
	Pre-Construction Meeting
	Time Schedule
Page 5	Wages of Employees on Public Works
Page 6-7	BDE Special Provisions Check Sheets
Page 8-20	BDE Special Provisions
Page 21-27	LR Special Provisions
Page 28	Project Location Map
Page 29	Quantity Sheet
Page 30-31	Typical Cross Sections
Page 32-34	Butt Joints
Page 35-42	Traffic Control Standards



Special Provisions



Local Public Agency	County	Section Number
Morton Road District	Tazewell	24-14000-01-GM
The following Special Provision supplement the "St	tandard Specifications for Road and I	Bridge Construction", adopted
January 1, 2022	igg] , the latest edition of the "Manual or	n Uniform Traffic Control Devices for
Streets and Highways", and the "Manual of Test Pr Supplemental Specification and Recurring Special govern the construction of the above named sectio Special Provisions shall take precedence and shall	Provisions indicated on the Check SIn, and in case of conflict with any part	heet included here in which apply to and
BIDDING REQUIREMENTS AND CONDI	·	ders with the Illinois Department of
Transportation is required.	r roqualification of bit	adere war are immere Beparament er
DESCRIPTION OF WORK: The work of and Hot-Mix Asphalt Surface Course, IL-9 work.		
TRAFFIC: TR 156A / Hires Trace shall remove the Morton Township Highway Commissioner construction to properly notify the property	r shall be notified a minimum 4	8 hours in advance of the start of
TRAFFIC CONTROL PLAN: Traffic Cont "Standard Specifications for Road and Bri "Manual on Uniform Traffic Control Device special details and Highway Standards co	idge Construction", the applica es for Streets and Highways",	able guidelines contained in the these Special Provisions, and any
Special attention is called to Articles 107. Bridge Construction" and the Traffic Conti 701306-04 and 701901-08 contained here	rol Standards 701006-05, 701	
The presence of temporary traffic control item or not, does not relieve the Contractor conditions warrant by the Engineer, all prospecial Provisions.	or of his obligation to the public	c. The Contractor shall provide, if
"NO PASSING ZONES NOT STRIPED N 701.17.	EXT MILES" signs shall b	pe posted in accordance with Article
Construction signs shall meet the current	Standard Specifications for Tr	affic Control Items.
Basis of payment: All required Traffic Col CONTROL & PROTECTION, (SPECIAL).	•	ntract-lump sum price for TRAFFIC
SUBSTITUTION OF BITUMINOUS MIXT substituted for the designs specified at the Engineer with an approved mix design at substitute mix shall be solely at the discretor under the same applicable articles as	e approval of the Engineer. The least 24 hours prior to its use etion of the Engineer. The new	ne contractor shall provide the for his review. Use of the proposed with mixture will be measured and paid

 Local Public Agency
 County
 Section Number

 Morton Road District
 Tazewell
 24-14000-01-GM

HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT:

The surface removal shall be performed according to Article 406.08 and Section 440.

Revise Article 440.06 Disposal of Material to read as follows: All milled material will remain the property of the Morton Township Road District and shall be transported from the job site to the Morton Township Road District storage yard located south of Hicks Gas at 27833 Cooper Road in Morton, Illinois behind Roanoke Farmers Association-Cooper Station grain elevator facility. Other sites may be determined by mutual agreement between the Contractor and the Road District. If other sites are approved, the Contractor will be responsible for preventing theft of milled material or unauthorized removal of said material from sites other than Morton Township Road District property.

Add the following to Article 440.08 Basis of Payment: Hauling of milled material shall be included in the cost of Hot-Mix Asphalt Surface Removal- Butt Joint and no extra compensation will be allowed.

HOT-MIX ASPHALT SURFACE REMOVAL:

Effective: March 1, 1993 Revised: January 1, 2022

The surface removal shall be performed in accordance to Section 440.

Description: This work shall consist of removing a portion of the existing hot-mix asphalt concrete surface course in accordance with the applicable portions of Section 440 and 1101 of the Standard Specifications, this special provision, details in the plans and as directed by the Engineer.

Revise Article 440.06 Disposal of Material to read as follows: All milled material will remain the property of the Morton Township Road District and shall be transported from the job site to the Morton Township Road District storage yard located at 27833 Cooper Road in Morton, Illinois behind Roanoke Farmers Association-Cooper Station grain elevator facility. Other sites may be determined by mutual agreement between the Contractor and the Road District. If other sites are approved, the Contractor will be responsible for preventing theft of milled material or unauthorized removal of said material from sites other than Morton Township Road District property.

Add the following to Article 440.08 Basis of Payment: Hauling of milled material shall be included in the cost of Hot-Mix Asphalt Surface Removal, 1 1/2" and no extra compensation will be allowed.

Equipment: The machine used for milling and planing shall be a self-propelled grinding machine having a minimum 12' wide drum at least 28" in diameter. When a milling width in excess of 12' is required and the Contractor's milling machine is less than the required width shown in the plans, the remaining area shall be milled with a machine capable of meeting the requirements of this special provision. Milling attachments used with skid steer tractors will not be allowed for longitudinal areas to mill additional widths.

When the teeth become worn so that they do not produce a uniform surface texture, they shall all be changed at the same time (as a unit). Occasionally, individual teeth may be changed if they lock up or break, but this method shall not be used to avoid changing the set of teeth as a unit. Occasional gouges, due to deteriorated pavement condition, or separation of lifts will not be cause to replace all teeth. The Engineer will be the sole judge of the cause of the pavement gouging and the corrective work required. Corrective work due to negligence or poor workmanship shall be at the Contractor's expense.

Local Public Agency	County	Section Number
Morton Road District	Tazewell	24-14000-01-GM

The moldboard is critical in obtaining the desired surface texture. It shall be straight, true, and free of excessive nicks or wear, and it shall be replaced as necessary to uniformly produce the required surface texture. Gouging of the pavement by more than 1/4 inch (6 mm) shall be sufficient cause to require replacement of all teeth.

Construction Requirements:

General: Weather conditions, when milling work is performed, must be such that short term or temporary pavement markings can be placed the day the surface is milled in accordance with Section 703 "Work Zone Pavement Markings".

An automatic grade control device shall be used when milling mainline pavement and shall be capable of controlling the elevation of the drum relative to either a preset grade control string line or a grade reference device traveling on the adjacent pavement surface. The automatic grade control device may be utilized only on one side of the machine with a automatic slope control device controlling the opposite side. The traveling grade reference device shall not be less than 30 feet in length. When milling cross roads, turn lanes, intersections, crossovers, or other miscellaneous areas, the Engineer may permit the matching shoe. The Contractor, at his option, may also substitute an approved 6' wide machine for areas other than mainline pavement.

The Contractor shall mill a depth according to the plans herein at the centerline and project the proposed cross slope to the edge of pavement. In the event the milling at the outer edge of the lane would exceed 1.50 inches; then the Contractor shall reduce the cut at the centerline to provide the maximum cut of 1.50 inches at the edge of pavement. If deemed necessary, the Contractor may reduce the cross slope from normal 1.5% to 1%.

Surface tests will be performed in accordance with Article 406.11 of the Standard Specifications. The longitudinal profile will be taken 3 ft. from and parallel to each edge of pavement and 3 ft. from and parallel to the centerline on each side. If a shadow area is found at the 3 ft. points the pavement smoothness tester will be moved sufficient distance either side to measure the Contractor's milling efforts. Any surface variations exceeding the tolerance in Article 406.11 shall be corrected by re-profiling at no additional expense to the Road District. In addition, the Contractor shall be responsible for refilling with approved hot-mix asphalt mixtures any area that lowered the pavement profile as a result of faulty milling operations if directed by the Engineer. The Contractor shall be responsible for providing the pavement smoothness tester described elsewhere to retest the pavement profile obtained.

If the milling depth is intended to expose the original concrete pavement, then additional hand or machine work may be necessary to remove any remaining veneer of bituminous pavement which may be left in place behind the milling machine. Such work will be at the direction of the Engineer and at no extra cost to the Road District.

The Contractor shall provide a 10 foot straightedge equipped with a carpenter's level or a 7 foot electronic straightedge to check the cross slope of the roadway at regular intervals as directed by the Engineer.

Surface Texture: Each tooth on the cutting drum shall produce a series of discontinuous longitudinal striations. There shall be 16 to 20 striations (tooth marks) for each tooth for each 6 feet in the longitudinal direction, and each striation shall be 1.7 inches \pm 0.2 inch in length after the area is planed by the moldboard. Thus, the planed length between each pair of striations shall be 2.3 inches \pm 0.2 inch. There shall be 80 to 96 rows of discontinuous longitudinal striations for each 5 feet in the transverse dimension.

Local Public Agency	County	Section Number
Morton Road District	Tazewell	24-14000-01-GM

The areas between the striations in both the longitudinal and transverse directions shall be flat topped and co-planer. The moldboard shall be used to cut this plane; and any time the operation fails to produce this flat plane interspersed with a uniform pattern of discontinuous longitudinal striations, the operation shall be stopped and the cause determined and corrected before recommencing. Other similar patterns of uniform discontinuous longitudinal striations interspersed on a flat plane may be approved by the Engineer. The drawing titled "Hot-Mix Asphalt Surface Removal" showing the desired surface texture is included in the plans.

The start-up milling speed shall be limited to a maximum of 50 feet per minute. The Contractor shall limit his operations to this speed to demonstrate his ability to obtain the striations and ride ability as described above. If the Contractor is able to demonstrate that he can consistently obtain the desired striations and ride ability at a greater speed he will be permitted to run at the increased speed.

Cleanup: After cold milling a traffic lane and before opening the lane to traffic, the pavement shall be swept by a self-propelled street sweeper with power vacuum capability to prevent compaction of the cuttings onto the pavement. All loose material shall be removed from the roadway. Before the prime coat is placed, the pavement shall be cleaned of all foreign material to the satisfaction of the Engineer.

This cleanup work shall be considered included in the contract unit price per Square Yard for HOT-MIX ASPHALT SURFACE REMOVAL of the depth specified, and no additional compensation will be allowed.

Method of Measurement:

- (a) Contract Quantities. The requirements for the use of Contract Quantities shall be Article 202.07(a) of the Standard Specifications.
- (b) Measured Quantities. Cold milling and planing will be measured and the area computed in square yards of surface.

Areas not milled (shadowed areas) due to rutting in the existing pavement surface will be included in the area measured for payment.

Basis of Payment: The work of this item will be paid for at the contract unit price per Square Yard for HOT-MIX ASPHALT SURFACE REMOVAL of the depth specified. Payment as specified will include variations in depth of cuts due to rutting, super elevations, and pavement crown and no additional compensation will be allowed.

<u>WEIGHT LIMITS:</u> Legal weight limits shall be observed on Morton Road District roads and structures they contain at all times.

GENERAL NOTES: Where section or subsection monuments are encountered, the Engineer shall be notified before such monuments are removed. The Contractor shall protect and carefully preserve all property markers and monuments until the owner, and authorized surveyor or agent has witnessed or otherwise referenced their location.

<u>PRE-CONSTRUCTION MEETING:</u> A pre-construction meeting for this Section is required between the Contractor, Highway Commissioner and the Resident Engineer.

TIME SCHEDULE: The specified completion date for this project is September 1, 2024.

Local Public Agency	County	Section Number
Morton Road District	Tazewell	24-14000-01-GM
WAGES OF EMPLOYEES ON PUBLIC WORKS: A Provision for Wages of Employees on Public Works, obtained from the IDOL (Illinois Department of Labor https://www2.illinois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/Linois.gov/idol/Laws-Rules/CONMED/linois.gov/idol/Laws-Rules/Linois.gov/idol/Laws-Rules/Linois.gov/idol/Laws-Rules/Linois.gov/idol/Laws-Rules/Linois.gov/idol/Laws-Rules/Linois.gov/idol/Laws-Rules/Linois.gov/linois.gov/idol/Linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/linois.gov/lino	Check Sheet LRS#12: Pre	•

BDE SPECIAL PROVISIONS For the April 26 and June 14, 2024 Lettings

The following special provisions indicated by a "check mark" are applicable to this contract and will be included by the Project Coordination and Implementation Section of the Bureau of Design & Environment (BDE).

<u>Fil</u>	e Name	#		Special Provision Title	Effective	Revised
	80099	1		Accessible Pedestrian Signals (APS)	April 1, 2003	Jan. 1, 2022
	80274	2		Aggregate Subgrade Improvement	April 1, 2012	April 1, 2022
	80192	3		Automated Flagger Assistance Devices	Jan. 1, 2008	April 1, 2023
	80173		П	Bituminous Materials Cost Adjustments	Nov. 2, 2006	Aug. 1, 2017
	80426		Ħ	Bituminous Surface Treatment with Fog Seal	Jan. 1, 2020	Jan. 1, 2022
*	80241		Ħ	Bridge Demolition Debris	July 1, 2009	.,
*	50531	7	Ħ	Building Removal	Sept. 1, 1990	Aug. 1, 2022
*		8	Ħ	Building Removal with Asbestos Abatement	Sept. 1, 1990	Aug. 1, 2022
	80449		Ħ	Cement, Type IL	Aug. 1, 2023	7 tag. 1, 2022
	80384		✓	Compensable Delay Costs	June 2, 2017	April 1, 2019
*	80198	11	Ħ	Completion Date (via calendar days)	April 1, 2008	, tp, 2010
*	80199	12	Ħ	Completion Date (via calendar days) Plus Working Days	April 1, 2008	
	80453	13	Ħ	Concrete Sealer	Nov. 1, 2023	
	80261	14	Ħ	Construction Air Quality – Diesel Retrofit	June 1, 2010	Nov. 1, 2014
	80434	15	Ħ	Corrugated Plastic Pipe (Culvert and Storm Sewer)	Jan. 1, 2021	1407. 1, 2014
*	80029	16	Ħ	Disadvantaged Business Enterprise Participation	Sept. 1, 2000	Mar. 2, 2019
		17	H	Fuel Cost Adjustment	April 1, 2009	Aug. 1, 2017
	80452	18	H	Full Lane Sealant Waterproofing System	Nov. 1, 2003	Aug. 1, 2017
	80447	19	H	Grading and Shaping Ditches	Jan. 1, 2023	
	80433		H	Green Preformed Thermoplastic Pavement Markings	Jan. 1, 2023	Jan. 1, 2022
	80443		H	High Tension Cable Median Barrier Removal	April 1, 2021	Jan. 1, 2022
	80456		片	•		
	80446		✓	Hot-Mix Asphalt Hot-Mix Asphalt - Longitudinal Joint Sealant	Jan. 1, 2024	Aug 1 2022
	80438		\Box	·	Nov. 1, 2022	Aug. 1, 2023
			H	Illinois Works Apprenticeship Initiative – State Funded Contracts	June 2, 2021	April 2, 2024
	80045		H	Material Transfer Device	June 15, 1999	Jan. 1, 2022
	80450			Mechanically Stabilized Earth Retaining Walls	Aug. 1, 2023	
	80441		✓	Performance Graded Asphalt Binder	Jan. 1, 2023	
*	80451		\mathbb{H}	Portland Cement Concrete	Aug. 1, 2023	1 4 0000
•	34261	29		Railroad Protective Liability Insurance	Dec. 1, 1986	Jan. 1, 2022
		30	√	Removal and Disposal of Regulated Substances	Jan. 1, 2024	April 1, 2024
	80445		Щ	Seeding	Nov. 1, 2022	
	80457		H	Short Term and Temporary Pavement Markings	April 1, 2024	
	80448		님	Source of Supply and Quality Requirements	Jan. 2, 2023	1 4 0000
	80340		닏	Speed Display Trailer	April 2, 2014	Jan. 1, 2022
	80127		님	Steel Cost Adjustment	April 2, 2004	Jan. 1, 2022
	80397		닏	Subcontractor and DBE Payment Reporting	April 2, 2018	4 11 4 00 40
	80391		\sqcup	Subcontractor Mobilization Payments	Nov. 2, 2017	April 1, 2019
	80437		Ц	Submission of Payroll Records	April 1, 2021	Nov. 2, 2023
	80435		Ц	Surface Testing of Pavements – IRI	Jan. 1, 2021	Jan. 1, 2023
	80410		Ц	Traffic Spotters	Jan. 1, 2019	_
*	20338		Ц	Training Special Provisions	Oct. 15, 1975	Sept. 2, 2021
	80429		닏	Ultra-Thin Bonded Wearing Course	April 1, 2020	Jan. 1, 2022
	80439		\checkmark	Vehicle and Equipment Warning Lights	Nov. 1, 2021	Nov. 1, 2022
	80302		Ш	Weekly DBE Trucking Reports	June 2, 2012	Nov. 1, 2021
	80454		Ш	Wood Sign Support	Nov. 1, 2023	
	80427		Ш	Work Zone Traffic Control Devices	Mar. 2, 2020	
*	80071	47		Working Days	Jan. 1, 2002	

Highlighted items indicate a new or revised special provision for the letting.

An * indicates the special provision requires additional information from the designer, which needs to be submitted separately. The Project Coordination and Implementation Section will then include the information in the applicable special provision.

The following special provisions are in the 2024 Supplemental Specifications and Recurring Special Provisions.

File Name	Special Provision Title	New Location(s)	<u>Effective</u>	Revised
80436	Blended Finely Divided Minerals	Articles 1010.01 & 1010.06	April 1, 2021	
80440	Waterproofing Membrane System	Article 1061.05	Nov. 1, 2021	

COMPENSABLE DELAY COSTS (BDE)

Effective: June 2, 2017 Revised: April 1, 2019

Revise Article 107.40(b) of the Standard Specifications to read:

- "(b) Compensation. Compensation will not be allowed for delays, inconveniences, or damages sustained by the Contractor from conflicts with facilities not meeting the above definition; or if a conflict with a utility in an unanticipated location does not cause a shutdown of the work or a documentable reduction in the rate of progress exceeding the limits set herein. The provisions of Article 104.03 notwithstanding, compensation for delays caused by a utility in an unanticipated location will be paid according to the provisions of this Article governing minor and major delays or reduced rate of production which are defined as follows.
 - (1) Minor Delay. A minor delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two hours, but not to exceed two weeks.
 - (2) Major Delay. A major delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two weeks.
 - (3) Reduced Rate of Production Delay. A reduced rate of production delay occurs when the rate of production on the work in conflict with the utility in an unanticipated location decreases by more than 25 percent and lasts longer than seven calendar days."

Revise Article 107.40(c) of the Standard Specifications to read:

- "(c) Payment. Payment for Minor, Major, and Reduced Rate of Production Delays will be made as follows.
 - (1) Minor Delay. Labor idled which cannot be used on other work will be paid for according to Article 109.04(b)(1) and (2) for the time between start of the delay and the minimum remaining hours in the work shift required by the prevailing practice in the area.
 - Equipment idled which cannot be used on other work, and which is authorized to standby on the project site by the Engineer, will be paid for according to Article 109.04(b)(4).
 - (2) Major Delay. Labor will be the same as for a minor delay.

Equipment will be the same as for a minor delay, except Contractor-owned equipment will be limited to two weeks plus the cost of move-out to either the

Contractor's yard or another job and the cost to re-mobilize, whichever is less. Rental equipment may be paid for longer than two weeks provided the Contractor presents adequate support to the Department (including lease agreement) to show retaining equipment on the job is the most economical course to follow and in the public interest.

(3) Reduced Rate of Production Delay. The Contractor will be compensated for the reduced productivity for labor and equipment time in excess of the 25 percent threshold for that portion of the delay in excess of seven calendar days. Determination of compensation will be in accordance with Article 104.02, except labor and material additives will not be permitted.

Payment for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be determined according to Article 109.13."

Revise Article 108.04(b) of the Standard Specifications to read:

- "(b) No working day will be charged under the following conditions.
 - (1) When adverse weather prevents work on the controlling item.
 - (2) When job conditions due to recent weather prevent work on the controlling item.
 - (3) When conduct or lack of conduct by the Department or its consultants, representatives, officers, agents, or employees; delay by the Department in making the site available; or delay in furnishing any items required to be furnished to the Contractor by the Department prevents work on the controlling item.
 - (4) When delays caused by utility or railroad adjustments prevent work on the controlling item.
 - (5) When strikes, lock-outs, extraordinary delays in transportation, or inability to procure critical materials prevent work on the controlling item, as long as these delays are not due to any fault of the Contractor.
 - (6) When any condition over which the Contractor has no control prevents work on the controlling item."

Revise Article 109.09(f) of the Standard Specifications to read:

"(f) Basis of Payment. After resolution of a claim in favor of the Contractor, any adjustment in time required for the work will be made according to Section 108. Any adjustment in the costs to be paid will be made for direct labor, direct materials, direct equipment, direct jobsite overhead, direct offsite overhead, and other direct costs allowed by the resolution. Adjustments in costs will not be made for interest charges, loss of anticipated profit, undocumented loss of efficiency, home office overhead and unabsorbed overhead

other than as allowed by Article 109.13, lost opportunity, preparation of claim expenses and other consequential indirect costs regardless of method of calculation.

The above Basis of Payment is an essential element of the contract and the claim cost recovery of the Contractor shall be so limited."

Add the following to Section 109 of the Standard Specifications.

"109.13 Payment for Contract Delay. Compensation for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be allowed when such costs result from a delay meeting the criteria in the following table.

Contract Type	Cause of Delay	Length of Delay
Working Days	Article 108.04(b)(3) or Article 108.04(b)(4)	No working days have been charged for two consecutive weeks.
Completion Date	Article 108.08(b)(1) or Article 108.08(b)(7)	The Contractor has been granted a minimum two week extension of contract time, according to Article 108.08.

Payment for each of the various costs will be according to the following.

- (a) Escalated Material and/or Labor Costs. When the delay causes work, which would have otherwise been completed, to be done after material and/or labor costs have increased, such increases will be paid. Payment for escalated material costs will be limited to the increased costs substantiated by documentation furnished by the Contractor. Payment for escalated labor costs will be limited to those items in Article 109.04(b)(1) and (2), except the 35 percent and 10 percent additives will not be permitted.
- (b) Extended Project Overhead. For the duration of the delay, payment for extended project overhead will be paid as follows.
 - (1) Direct Jobsite and Offsite Overhead. Payment for documented direct jobsite overhead and documented direct offsite overhead, including onsite supervisory and administrative personnel, will be allowed according to the following table.

Original Contract Amount	Supervisory and Administrative Personnel
Up to \$5,000,000	One Project Superintendent
Over \$ 5,000,000 - up to \$25,000,000	One Project Manager, One Project Superintendent or Engineer, and One Clerk
Over \$25,000,000 - up to \$50,000,000	One Project Manager, One Project Superintendent, One Engineer, and

	One Clerk
Over \$50,000,000	One Project Manager,
	Two Project Superintendents,
	One Engineer, and
	One Clerk

- (2) Home Office and Unabsorbed Overhead. Payment for home office and unabsorbed overhead will be calculated as 8 percent of the total delay cost.
- (c) Extended Traffic Control. Traffic control required for an extended period of time due to the delay will be paid for according to Article 109.04.

When an extended traffic control adjustment is paid under this provision, an adjusted unit price as provided for in Article 701.20(a) for increase or decrease in the value of work by more than ten percent will not be paid.

Upon payment for a contract delay under this provision, the Contractor shall assign subrogation rights to the Department for the Department's efforts of recovery from any other party for monies paid by the Department as a result of any claim under this provision. The Contractor shall fully cooperate with the Department in its efforts to recover from another party any money paid to the Contractor for delay damages under this provision."

80384

HOT-MIX ASPHALT (BDE)

Effective: January 1, 2024

Revise the second paragraph of Articles 1030.07(a)(11) and 1030.08(a)(9) of the Standard Specifications to read:

"When establishing the target density, the HMA maximum theoretical specific gravity (G_{mm}) will be based on the running average of four available Department test results for that project. If less than four G_{mm} test results are available, an average of all available Department test results for that project will be used. The initial G_{mm} will be the last available Department test result from a QMP project. If there is no available Department test result from a QMP project, the Department mix design verification test result will be used as the initial G_{mm} ."

In the Supplemental Specifications, replace the revision for the end of the third paragraph of Article 1030.09(h)(2) with the following:

"When establishing the target density, the HMA maximum theoretical specific gravity (G_{mm}) will be the Department mix design verification test result."

Revise the tenth paragraph of Article 1030.10 of the Standard Specifications to read:

"Production is not required to stop after a test strip has been constructed."

80456

PERFORMANCE GRADED ASPHALT BINDER (BDE)

Effective: January 1, 2023

Revise Article 1032.05 of the Standard Specifications to read:

"1032.05 Performance Graded Asphalt Binder. These materials will be accepted according to the Bureau of Materials Policy Memorandum, "Performance Graded Asphalt Binder Qualification Procedure." The Department will maintain a qualified producer list. These materials shall be free from water and shall not foam when heated to any temperature below the actual flash point. Air blown asphalt, recycle engine oil bottoms (ReOB), and polyphosphoric acid (PPA) modification shall not be used.

When requested, producers shall provide the Engineer with viscosity/temperature relationships for the performance graded asphalt binders delivered and incorporated in the work.

(a) Performance Graded (PG) Asphalt Binder. The asphalt binder shall meet the requirements of AASHTO M 320, Table 1 "Standard Specification for Performance Graded Asphalt Binder" for the grade shown on the plans and the following.

Test	Parameter
Small Strain Parameter (AASHTO PP 113) BBR, ΔTc, 40 hrs PAV (40 hrs continuous or 2 PAV at 20 hrs)	-5 °C min.

(b) Modified Performance Graded (PG) Asphalt Binder. The asphalt binder shall meet the requirements of AASHTO M 320, Table 1 "Standard Specification for Performance Graded Asphalt Binder" for the grade shown on the plans.

Asphalt binder modification shall be performed at the source, as defined in the Bureau of Materials Policy Memorandum, "Performance Graded Asphalt Binder Qualification Procedure."

Modified asphalt binder shall be safe to handle at asphalt binder production and storage temperatures or HMA construction temperatures. Safety Data Sheets (SDS) shall be provided for all asphalt modifiers.

(1) Polymer Modification (SB/SBS or SBR). Elastomers shall be added to the base asphalt binder to achieve the specified performance grade and shall be either a styrene-butadiene diblock, triblock copolymer without oil extension, or a styrenebutadiene rubber. The polymer modified asphalt binder shall be smooth, homogeneous, and be according to the requirements shown in Table 1 or 2 for the grade shown on the plans.

Table 1 - Requirements for Styrene-Butadiene Copolymer (SB/SBS) Modified Asphalt Binders			
Test	Asphalt Grade SB/SBS PG 64-28 SB/SBS PG 70-22	Asphalt Grade SB/SBS PG 64-34 SB/SBS PG 70-28 SB/SBS PG 76-22 SB/SBS PG 76-28	
Separation of Polymer ITP, "Separation of Polymer from Asphalt Binder" Difference in °F (°C) of the softening point between top and bottom portions	4 (2) max.	4 (2) max.	
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	60 min.	70 min.	

Table 2 - Requirements for Styrene-Butadiene Rubber (SBR) Modified Asphalt Binders		
Test	Asphalt Grade SBR PG 64-28 SBR PG 70-22	Asphalt Grade SB/SBS PG 64-34 SB/SBS PG 70-28 SBR PG 76-22 SBR PG 76-28
Separation of Polymer		
ITP, "Separation of Polymer from Asphalt Binder"		
Difference in °F (°C) of the softening		
point between top and bottom portions	4 (2) max.	4 (2) max.
Toughness	, ,	, ,
ASTM D 5801, 77 °F (25 °C),		
20 in./min. (500 mm/min.), inlbs (N-m)	110 (12.5) min.	110 (12.5) min.
Tenacity ASTM D 5801, 77 °F (25 °C),		
20 in./min. (500 mm/min.), inlbs (N-m)	75 (8.5) min.	75 (8.5) min.
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)		
Elastic Recovery		
ASTM D 6084, Procedure A,		
77 °F (25 °C), 100 mm elongation, %	40 min.	50 min.

(2) Ground Tire Rubber (GTR) Modification. GTR modification is the addition of recycled ground tire rubber to liquid asphalt binder to achieve the specified performance grade. GTR shall be produced from processing automobile and/or truck tires by the ambient

grinding method or micronizing through a cryogenic process. GTR shall not exceed 1/16 in. (2 mm) in any dimension and shall not contain free metal particles, moisture that would cause foaming of the asphalt, or other foreign materials. A mineral powder (such as talc) meeting the requirements of AASHTO M 17 may be added, up to a maximum of four percent by weight of GTR to reduce sticking and caking of the GTR particles. When tested in accordance with Illinois Modified AASHTO T 27 "Standard Method of Test for Sieve Analysis of Fine and Coarse Aggregates" or AASHTO PP 74 "Standard Practice for Determination of Size and Shape of Glass Beads Used in Traffic Markings by Means of Computerized Optical Method", a 50 g sample of the GTR shall conform to the following gradation requirements.

Sieve Size	Percent Passing
No. 16 (1.18 mm)	100
No. 30 (600 µm)	95 ± 5
No. 50 (300 µm)	> 20

GTR modified asphalt binder shall be tested for rotational viscosity according to AASHTO T 316 using spindle S27. GTR modified asphalt binder shall be tested for original dynamic shear and RTFO dynamic shear according to AASHTO T 315 using a gap of 2 mm.

The GTR modified asphalt binder shall meet the requirements of Table 3.

Table 3 - Requirements for Ground Tire Rubber (GTR) Modified Asphalt Binders			
Test	Asphalt Grade GTR PG 64-28 GTR PG 70-22	Asphalt Grade GTR PG 76-22 GTR PG 76-28 GTR PG 70-28	
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	60 min.	70 min.	

(3) Softener Modification (SM). Softener modification is the addition of organic compounds, such as engineered flux, bio-oil blends, modified vegetable oils, glycol amines, and fatty acid derivatives, to the base asphalt binder to achieve the specified performance grade. Softeners shall be dissolved, dispersed, or reacted in the asphalt binder to enhance its performance and shall remain compatible with the asphalt binder with no separation. Softeners shall not be added to modified PG asphalt binder as defined in Articles 1032.05(b)(1) or 1032.05(b)(2).

An Attenuated Total Reflectance-Fourier Transform Infrared spectrum (ATR-FTIR) shall be collected for both the softening compound as well as the softener modified

asphalt binder at the dose intended for qualification. The ATR-FTIR spectra shall be collected on unaged softener modified binder, 20-hour Pressurized Aging Vessel (PAV) aged softener modified binder, and 40-hour PAV aged softener modified binder. The ATR-FTIR shall be collected in accordance with Illinois Test Procedure 601. The electronic files spectral files (in one of the following extensions or equivalent: *.SPA, *.SPG, *.IRD, *.IFG, *.CSV, *.SP, *.IRS, *.GAML, *.[0-9], *.IGM, *.ABS, *.DRT, *.SBM, *.RAS) shall be submitted to the Central Bureau of Materials.

Softener modified asphalt binders shall meet the requirements in Table 4.

Table 4 - Requirements for Softener Modified Asphalt Binders		
	Asphalt Grade	
Test	SM PG 46-28	SM PG 46-34
	SM PG 52-28	SM PG 52-34
	SM PG 58-22	SM PG 58-28
	SM PG 64-22	
Small Strain Parameter (AASHTO PP 113)		
BBR, ΔTc, 40 hrs PAV (40 hrs	-5°C min.	
continuous or 2 PAV at 20 hrs)		
Large Strain Parameter (Illinois Modified		
AASHTO T 391) DSR/LAS Fatigue	≥ 54 %	
Property, Δ G* peak τ, 40 hrs PAV		
(40 hrs continuous or 2 PAV at 20 hrs)		

The following grades may be specified as tack coats.

Asphalt Grade	Use
PG 58-22, PG 58-28, PG 64-22	Tack Coat"

Revise Article 1031.06(c)(1) and 1031.06(c)(2) of the Standard Specifications to read:

"(1) RAP/RAS. When RAP is used alone or RAP is used in conjunction with RAS, the percentage of virgin ABR shall not exceed the amounts listed in the following table.

HMA Mixtures - RAP/RAS Maximum ABR % 1/2/				
Ndesign	Binder	Surface	Polymer Modified Binder or Surface ^{3/}	
30	30	30	10	
50	25	15	10	
70	15	10	10	
90	10	10	10	

1/ For Low ESAL HMA shoulder and stabilized subbase, the RAP/RAS ABR shall not exceed 50 percent of the mixture.

- 2/ When RAP/RAS ABR exceeds 20 percent, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- 3/ The maximum ABR percentages for ground tire rubber (GTR) modified mixes shall be equivalent to the percentages specified for SBS/SBR polymer modified mixes.
- (2) FRAP/RAS. When FRAP is used alone or FRAP is used in conjunction with RAS, the percentage of virgin asphalt binder replacement shall not exceed the amounts listed in the following table.

HMA Mixtures - FRAP/RAS Maximum ABR % 1/2/				
Ndesign	Binder	Surface	Polymer Modified Binder or Surface ^{3/}	
30	55	45	15	
50	45	40	15	
70	45	35	15	
90	45	35	15	
SMA			25	
IL-4.75			35	

- 1/ For Low ESAL HMA shoulder and stabilized subbase, the FRAP/RAS ABR shall not exceed 50 percent of the mixture.
- 2/ When FRAP/RAS ABR exceeds 20 percent for all mixes, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- 3/ The maximum ABR percentages for GTR modified mixes shall be equivalent to the percentages specified for SBS/SBR polymer modified mixes."

Add the following to the end of Note 2 of Article 1030.03 of the Standard Specifications.

"A dedicated storage tank for the ground tire rubber (GTR) modified asphalt binder shall be provided. This tank shall be capable of providing continuous mechanical mixing throughout and/or recirculation of the asphalt binder to provide a uniform mixture. The tank shall be heated and capable of maintaining the temperature of the asphalt binder at 300 °F to 350 °F (149 °C to 177 °C). The asphalt binder metering systems of dryer drum plants shall be calibrated with the actual GTR modified asphalt binder material with an accuracy of ± 0.40 percent."

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)

Effective: January 1, 2024 Revised: April 1, 2024

Revise the first paragraph of Article 669.04 of the Standard Specifications to read:

"669.04 Regulated Substances Monitoring. Regulated substances monitoring includes environmental observation and field screening during regulated substances management activities. The excavated soil and groundwater within the work areas shall be managed as either uncontaminated soil, hazardous waste, special waste, or non-special waste.

As part of the regulated substances monitoring, the monitoring personnel shall perform and document the applicable duties listed on form BDE 2732 "Regulated Substances Monitoring Daily Record (RSMDR)"."

Revise the first two sentences of the nineteenth paragraph of Article 669.05 of the Standard Specifications to read:

"The Contractor shall coordinate waste disposal approvals with the disposal facility and provide the specific analytical testing requirements of that facility. The Contractor shall make all arrangements for collection, transportation, and analysis of landfill acceptance testing."

Revise the last paragraph of Article 669.05 of the Standard Specifications to read:

"The Contractor shall select a permitted landfill facility or CCDD/USFO facility meeting the requirements of 35 III. Admin. Code Parts 810-814 or Part 1100, respectively. The Department will review and approve or reject the facility proposed by the Contractor based upon information provided in BDE 2730. The Contractor shall verify whether the selected facility is compliant with those applicable standards as mandated by their permit and whether the facility is presently, has previously been, or has never been, on the United States Environmental Protection Agency (U.S. EPA) National Priorities List or the Resource Conservation and Recovery Act (RCRA) List of Violating Facilities. The use of a Contractor selected facility shall in no manner delay the construction schedule or alter the Contractor's responsibilities as set forth."

Revise the first paragraph of Article 669.07 of the Standard Specifications to read:

"669.07 Temporary Staging. Soil classified according to Articles 669.05(a)(2), (b)(1), or (c) may be temporarily staged at the Contractor's option. All other soil classified according to Articles 669.05(a)(1), (a)(3), (a)(4), (a)(5), (a)(6), or (b)(2) shall be managed and disposed of without temporary staging to the greatest extent practicable. If circumstances beyond the Contractor's control require temporary staging of these latter materials, the Contractor shall request approval from the Engineer in writing.

Topsoil for re-use as final cover which has been field screened and found not to exhibit PID readings over daily background readings as documented on the BDE 2732, visual staining or

odors, and is classified according to Articles 669.05(a)(2), (a)(3), (a)(4), (b)(1), or (c) may be temporarily staged at the Contractor's option."

Add the following paragraph after the sixth paragraph of Article 669.11 of the Standard Specifications.

"The sampling and testing of effluent water derived from dewatering discharges for priority pollutants volatile organic compounds (VOCs), priority pollutants semi-volatile organic compounds (SVOCs), or priority pollutants metals, will be paid for at the contract unit price per each for VOCS GROUNDWATER ANALYSIS using EPA Method 8260B, SVOCS GROUNDWATER ANALYSIS using EPA Methods 8270C, or RCRA METALS GROUNDWATER ANALYSIS using EPA Methods 6010B and 7471A. This price shall include transporting the sample from the job site to the laboratory."

Revise the first sentence of the eight paragraph of Article 669.11 of the Standard Specifications to read:

"Payment for temporary staging of soil classified according to Articles 669.05(a)(1), (a)(3), (a)(4), (a)(5), (a)(6), or (b)(2) to be managed and disposed of, if required and approved by the Engineer, will be paid according to Article 109.04."

80455

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)

Effective: November 1, 2021 Revised: November 1, 2022

Add the following paragraph after the first paragraph of Article 701.08 of the Standard Specifications:

"The Contractor shall equip all vehicles and equipment with high-intensity oscillating, rotating, or flashing, amber or amber-and-white, warning lights which are visible from all directions. In accordance with 625 ILCS 5/12-215, the lights may only be in operation while the vehicle or equipment is engaged in construction operations."

80439

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR INSURANCE

Effective: February 1, 2007 Revised: August 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

The Contractor shall name the following entities as additional insured under the Contractor's general liability insurance policy in accordance with Article 107.27:

Morton Road District			
Tazewell County			

The entities listed above and their officers, employees, and agents shall be indemnified and held harmless in accordance with Article 107.26.

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR EQUIPMENT RENTAL RATES

Effective: January 1, 2012

All references to Sections or Articles in this specification shall be construed to mean a specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

Replace Article 109.04(b)(4) with the following:

"(4) Equipment. For any machinery or special equipment (other than small tools) the use of which has been authorized by the Engineer, the Contractor will be paid according to the latest revision of "SCHEDULE OF AVERAGE ANNUAL EQUIPMENT OWNERSHIP EXPENSE" and latest index factor as issued by the Illinois Department of Transportation. The equipment should be of a type and size reasonably required to complete the extra work."

State of Illinois DEPARTMENT OF TRANSPORTATION Bureau of Local Roads & Streets SPECIAL PROVISION

FOR

LOCAL QUALITY ASSURANCE/ QUALITY MANAGEMENT QC/QA Effective: January 1, 2022

Replace the first five paragraphs of Article 1030.06 of the Standard Specifications with the following:

"1030.06 Quality Management Program. The Quality Management Program (QMP) will be Quality Control / Quality Assurance (QC/QA) according to the following."

Delete Article 1030.06(d)(1) of the Standard Specifications.

Revise Article 1030.09(g)(3) of the Standard Specifications to read:

"(3) If core testing is the density verification method, the Contractor shall provide personnel and equipment to collect density verification cores for the Engineer. Core locations will be determined by the Engineer following the document "Hot-Mix Asphalt QC/QA Procedure for Determining Random Density Locations" at density verification intervals defined in Article 1030.09(b). After the Engineer identifies a density verification location and prior to opening to traffic, the Contractor shall cut a 4 in. (100 mm) diameter core. With the approval of the Engineer, the cores may be cut at a later time."

Revise Article 1030.09(h)(2) of the Standard Specifications to read:

"(2) After final rolling and prior to paving subsequent lifts, the Engineer will identify the random density verification test locations. Cores or nuclear density gauge testing will be used for density verification. The method used for density verification will be as selected below

	Density Verification Method						
	Cores						
\square							
	paving ≥ 3,000 tons per mixture)						

Density verification test locations will be determined according to the document "Hot-Mix Asphalt QC/QA Procedure for Determining Random Density Locations". The density testing interval for paving wider than or equal to 3 ft (1 m) will be 0.5 miles (800 m) for lift thicknesses of 3 in. (75 mm) or less and 0.2 miles (320 m) for lift thicknesses greater than 3 in. (75 mm). The density testing interval for paving less than 3 ft (1 m) wide will be 1 mile (1,600 m). If a day's paving will be less than the prescribed density testing interval, the length of the day's paving will be the interval for that day. The density testing interval for mixtures used for patching will be 50 patches with a minimum of one test per mixture per project.

If core testing is the density verification method, the Engineer will witness the Contractor coring, and secure and take possession of all density samples at the

density verification locations. The Engineer will test the cores collected by the Contractor for density according to Illinois Modified AASHTO T 166 or AASHTO T 275.

If nuclear density gauge testing is the density verification method, the Engineer will conduct nuclear density gauge tests. The Engineer will follow the density testing procedure detailed in the document "Illinois Modified ASTM D 2950, Standard Test Method for Density of Bituminous Concrete In-Place by Nuclear Method".

A density verification test will be the result of a single core or the average of the nuclear density tests at one location. The results of each density test must be within acceptable limits. The Engineer will promptly notify the Contractor of observed deficiencies."

Revise the seventh paragraph and all subsequent paragraphs in Section D. of the document "Hot-Mix Asphalt QC/QA Initial Daily Plant and Random Samples" to read:

"Mixtures shall be sampled from the truck at the plant by the Contractor following the same procedure used to collect QC mixture samples (Section A). This process will be witnessed by the Engineer who will take custody of the verification sample. Each sample bag with a verification mixture sample will be secured by the Engineer using a locking ID tag. Sample boxes containing the verification mixture sample will be sealed/taped by the Engineer using a security ID label."

State of Illinois DEPARTMENT OF TRANSPORTATION Bureau of Local Roads & Streets

SPECIAL PROVISION FOR EMULSIFIED ASPHALTS

Effective: January 1, 2007 Revised: February 7, 2008

All references to Sections and Articles in this Special Provision shall be construed to mean specific Sections and Articles in the Standard Specifications for Road and Bridge Construction adopted by the Department of Transportation.

Replace the table after Note 2 in Article 403.02 with the following:

	Bituminous Materials Recommended for Weather Conditions Indicated					
Type of Construction	Warm [15 °C to 30 °C]* [(60 °F to 85 °F)]*	Hot [30 °C Plus]* [(85 °F Plus)]*				
Prime	MC-30, PEP	MC-30, PEP				
Cover Coat and Seal Coat	RS-2, CRS-2, RC-800, RC-3000, MC-800, MC-3000, SC-3000, HFE-90, HFE-150, HFE-300, HFRS-2, PEA**	RS-2, CRS-2, RC-800, RC-3000, MC-800, MC-3000, SC-3000, PG46-28, PG52-28, HFE-90, HFE-150, HFE-300, HFRS-2, PEA**				

- * Temperature of the air in the shade at the time of application.
- ** PEA is only allowed on roads with low traffic volumes

Replace the table after Note 2 in Article 406.02 with the following:

Type of Construction	Bituminous Materials Recommended
Prime (tack) on Brick, Concrete, or Bituminous Bases (Note 3)	SS-1, SS-1h, CSS-1, CSS-1h, HFE-90, RC-70
Prime on Aggregate Bases (Note 4)	MC-30, PEP
Mixture for Cracks, Joints, and Flangeways	PG58-22, PG64-22

- Note 3. When emulsified asphalts are used, they shall be diluted with an equal volume of potable water. HFE emulsions shall be diluted by the manufacturer. The diluted material shall be thoroughly agitated within 24 hours of application and show no separation of water and emulsion. The diluted material shall not be returned to an approved emulsion storage tank.
- Note 4. Preparation of the bituminous PEP shall be as specified in Article 403.05.

Spraying Application Temperature Ranges						
Type and Crade of	Temperatu	ıre Ranges				
Type and Grade of Bituminous Material	°F	°C				
Biturninous Material	min max.	min max.				
PEP	60 - 130	15 - 55				
PEA	140 - 190	60 -88				
MC-30	85 - 190	30 - 90				
MC-70, RC-70, SC-70	120 - 225	50 - 105				
MC-250, SC-250	165 - 270	75 - 130				
MC-800, SC-800	200 - 305	95 - 150				
MC-3000, SC-3000	230 - 345	110 - 175				
PG46-28	275 - 385	135 - 195				
PG52-28	285 - 395	140 - 200				
RS-2, CRS-2	110 - 160	45 - 70				
SS-1, SS-1h, CSS-1, CSS-1h	75 - 130	25 - 55				
SS-1hP, CSS-1hP	75 - 130	25 - 55				
HFE-90, HFE-150, HFE-300	150 - 180	65 - 80				
HFP, CRSP, HFRS-2	150 - 180	65 - 80				
E-2	85 - 190	30 - 90				
E-3	120 - 225	50 - 105				
E-4	165 - 270	75 - 130				

Add subparagraph (g) to Article 1032.06:

(g) Penetrating Emulsified Asphalt (PEA). The penetrating emulsified asphalt shall meet the following requirements when tested according to AASHTO T59:


Viscosity, Saybolt Fural @ 25°C (77°F),	sec:	20 - 500
Sieve Test, retained on 850 μm (No. 20) sieve, maximum, Storage Stability Test, 1 day, maximum,	%: %:	0.10
Float Test @ 60°C (140°F), minimum,	sec:	150
Stone Coating Test, 3 minutes,	:	Stone Coated Thoroughly
Particle Charge	:	Negative
pH, minimum	:	7.3
Distillation Test:		
Distillation to 260°C (500°F) Residue, minimum	%:	65
Oil Distillate by Volume, maximum	%:	3
Test on residue from distillation:		
Penetration @ 25°C (77°F), 100 g, 5 sec, minimum	dmm:	300

Replace the last sentence and table of Article 1032.06 with the following:

The different grades are, in general, used for the following.

Grade	Use
SS-1, SS-1h, CSS-1, CSS-1h, HFE 90, SS-1hP, CSS-1hP	Tack or fog seal
PEP	Bituminous surface treatment prime
RS-2, HFE 90, HFE 150, HFE 300, CRSP, HFP, CRS-2, HFRS-2, PEA	Bituminous surface treatment
CSS-1h Latex Modified	Microsurfacing


MORTON ROAD DISTRICT TWP. 25N, R 3W, 3rd P.M. 24-14000-01-GM



QUANTITIES

Route/Section TR 156A / Hires Trace **Includes Radii & Cul-De-		<u>Width (ft)</u> 37	<u>Area (SY)</u> <u>6,104</u>	
Hot-Mix Asphalt Surface I 22.5' x 50' @ Veterans	Removal-Butt Jo	int:	140	SQ YD
Hot-Mix Asphalt Surface I Curb Section	Removal, 1 1/2"		4,623	SQ YD
Temporary Ramp: 50' x 4'			22	SQ YD
Polymerized Bituminous I Rate = 0.72 lbs/SY	Materials (Tack (Coat):	4,395	POUND
Hot-Mix Asphalt Surface 6 6,104 SQ YD x 112# x 1.50		<u>1ix "C", N50:</u>	513	TON
Traffic Control and Protect	ction, (Special):		1	L SUM

TYPICAL CROSS SECTION TR 156A / HIRES TRACE



Location:	TR 156A / Hires	Trace
Mixture Uses:		Surface Course
PG:		PG 58-28
Design Air Voids:		4.0 @ N50
Mixture Composition: (Gradation Mixture)		IL 9.5
Friction Aggregate:		Mixture C


Section: 24-14000-01-GM

Route: TR 156A / HIRES TRACE Location: Veterans Rd Northerly to

EOR Cul-De-Sac

Sheet 1 of 2

TYPICAL CROSS SECTION TR 156A / HIRES TRACE




Location:	s Trace	
Mixture Uses:		Surface Course
PG:		PG 58-28
Design Air Voids:		4.0 @ N50
Mixture Composition: (Gradation Mixture)		IL 9.5
Friction Aggregate:		Mixture C

Section: 24-14000-01-GM

Route: TR 156A / HIRES TRACE Location: Veterans Rd Northerly to

EOR Cul-De-Sac

Sheet 2 of 2




CASE 1: WITH HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING)

TABLE A TAPER RATES

SPECIAL NOTE	ELEMENT	MAINLINE INTERSTATES &	ALL
NUMBER		4-LANE EXPRESSWAYS	OTHERS
(1)	BUTT JOINT	1:480	1:240
	TAPER RATE		
(2)	TEMPORARY RAMP	1:80	1:40
	TAPER RATE		

GENERAL NOTES


- 1. The work shall be done in accordance with Article 406.08 and the Special Provision for Butt Joints.
- 2. The pavement surface to be removed may be either bituminous or P.C. concrete. The work shall be performed in accordance with Article 440.04 and the Special Provisions for Butt Joints.
- 3. The saw cut joints shall be primed just prior to the placing of bituminous material. The work will be in accordance with the applicable portions of Article 406.05.
- 4. The length of butt joint is based on the taper rate times change in cold milling depth within the butt joint pay limits, unless otherwise indicated.
- 5. Temporary ramps are paid for separately and not included in the cost of the butt joints.




CASE 2 : NO HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING)

All dimensions are in inches (millimeters) unless otherwise noted.

0	01-01-97	RENUM. C-23.01, NEW REVISION BOX	T.P.	08-21-13 MAJOR MODIFICATIONS	R.D.				F.A.	SECTION COUNTY	SHEETS NO.
0	04-01-97	CORRECTION TO DEPTH	J.A.	04-12-16 MINOR CORRECTIONS	R.D.	STATE OF ILLINOIS	BUTT JOINTS				SHEETS NO.
0	9-15-05	REVISED DESIGNER NOTE	M.M.A.	02-14-17 ADDED NOTE 5	R.D.	DEPARTMENT OF TRANSPORTATION		SHT. 1 OF 3		CONTRA	CT NO.
10	0-16-06	REVISED TO 2007 SPEC.	M.A.	07-16-19 Wording and Spelling corrections	R.D.	Page 32	NOT TO SCALE	CADD STD. 406101-D4	FED. ROAD DIST. NO	. ILLINOIS FED. AID PROJECT	




CASE 3: HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING) TIE-IN TO EXISTING BITUMINOUS TAPER



All dimensions are in inches (millimeters) unless otherwise noted.

						F.A. RTF.	SECTION	COUNTY	TOTAL SHEET
		STATE OF ILLINOIS		BUTT JOINTS					1
		DEPARTMENT OF TRANSPORTATION			SHT. 2 OF 3			CONTRACT	NO.
		Page 33	NOT TO SCALE		CADD STD. 406101-D4	FED. ROA	AD DIST. NO. ILLINOIS FED. AI	D PROJECT	




CASE 4 : SINGLE LIFT OVERLAY WITH EQUIVALENT DEPTH

HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING)

TIE-IN TO EXISTING BITUMINOUS TAPER

All dimensions are in inches (millimeters) unless otherwise noted.

					F.A. RTF.	SECTION	COUNTY	TOTAL SHEET
		STATE OF ILLINOIS	BUTT JOINTS					
		DEPARTMENT OF TRANSPORTATION		SHT. 3 OF 3			CONTRAC	T NO.
		Page 34	NOT TO SCALE	CADD STD. 406101-D4	FED. R	OAD DIST. NO. ILLINOIS FED. A	AID PROJECT	



TYPICAL APPLICATIONS

Utility operations Culvert extensions Side slope changes Guardrail installation and maintenance Delineator installation Landscaping operations Shoulder repair Sign installation and maintenance

Work area

SYMBOLS

O Cone, drum or barricade

1) When the work operation exceeds one hour, cones, drums or barricades shall be placed at 25' (8 m) centers for L/3 distance, and at 50' (15 m) centers through the remainder of the work area.

GENERAL NOTES

This Standard is used where any vehicles, equipment, workers or their activities will encroach in the area 15' (4.5 m) to 24 (600) from the edge of pavement.

Calculate L as follows:

SPEED LIMIT FORMULAS

> English (Metric)

40 mph (70 km/h)

 $L = \frac{WS^2}{150}$

45 mph (80 km/h) or greater:

or less:

L=0.65(W)(S) L=(W)(S)

W = Width of offset in feet (meters).

S = Normal posted speed mph (km/h).

All dimensions are in inches (millimeters) unless otherwise shown.


DATE	REVISIONS	
1-1-14	Revised workers sign	
	number to agree with	
	current MUTCD.	
1-1-13	Omitted text 'WORKERS'	_
	sign.	


		GINESE STITES SITE WITE
)ATE	REVISIONS	OFF-RD OPERATIONS, 2L, 2W,
1-14	Revised workers sign	
	number to agree with	15' (4.5 m) TO 24" (600 mm)
	current MUTCD.	FROM PAVEMENT EDGE
1-13	Omitted text 'WORKERS'	
	sian	074ND4DD 704000 05


STANDARD 701006-05


Illinois Department of Transportation


ENGINEER OF SAFETY ENGINEERING APPROVED January 1,















POST MOUNTED SIGNS

** When curb or paved shoulder are present this dimension shall be 24 (600) to the face of curb or 6' (1.8 m) to the outside edge of the paved shoulder.


24 - 10' (600 - 3 m) Edge of pavement or face of curb Elevation of edge of pavement

SIGNS ON TEMPORARY SUPPORTS

*** When work operations exceed four days, this dimension shall be 5' (1.5 m) min. If located behind other devices, the height shall be sufficient to be seen completely above the devices.




HIGH LEVEL WARNING DEVICE



WIDTH RESTRICTION SIGN

XX'-XX" width and X miles are variable.



ROAD CONSTRUCTION NEXT X MILES

END CONSTRUCTION

G20-I104(0)-6036

G20-I105(0)-6024


This signing is required for all projects 2 miles (3200 m) or more in length.

ROAD CONSTRUCTION NEXT X MILES sign shall be placed 500' (150 m) in advance of project limits.

END CONSTRUCTION sign shall be erected at the end of the job unless another job is within 2 miles (3200 m).

Dual sign displays shall be utilized on multilane highways.

WORK LIMIT SIGNING



Sign assembly as shown on Standards or as allowed by District Operations.



This sign shall be used when the above sign assembly is used.

HIGHWAY CONSTRUCTION SPEED ZONE SIGNS

**** R10-I108p shall only be used along roadways under the juristiction of the State.

TRAFFIC CONTROL **DEVICES**

(Sheet 2 of 3)

STANDARD 701901-09

FLAGGER TRAFFIC CONTROL SIGN

APPROVED.

Illinois Department of Transportation

