Tazewell County Highway Department

AUTHORIZATION TO BID FORM

Addenda will be published to our Bid Letting page in the same manner as the plans and specifications. It is the sole responsibility of the plan holders to periodically check the website for plan addenda.

ALL BIDDERS PLANNING TO PLACE A BID MUST FILL OUT THIS FORM TO BE AUTHORIZED TO BID.

- This form must be completed, signed and either faxed to (309) 925-5533 or emailed to jsciortino@tazewell-il.gov.
- Failure to submit this completed form will result in the bid not being accepted.
- Contractors may verify we have received their Authorization to Bid form by checking the **Plan Holders List** found under the corresponding letting date.
- If an email address is provided, a Notice of Addenda will be sent when updates are available.
- Bid results are typically posted by noon on the day of the letting and are preliminary until approved by the County Board on the last Wednesday of the month.

Company Name:	
Address:	
///////////////////////////////////////	
Phone:	
Fax:	
Email:	
Bid Letting Date:	

Projects Intending to Bid on:

Section Number:	Description:

Tazewell County Highway Department 21308 Illinois Route 9 Tremont, IL 61568 p: (309) 925-5532 • f: (309) 925-5533 • jsciortino@tazewell-il.gov



COVER	SHEET			
Proposal Submitted By:				
Contractor's Name				
Contractor's Address	City			State Zip Code
STATE OF ILLINOIS				
Local Public Agency		County		ection Number
Washington Road District		Tazewell	2	5-19000-01-GM(N-MFT)
Route(s) (Street/Road Name)			Type of Fund	ls
TR 15-D/Guth Rd. & TR 21/Irish Ln.			Township	Non-MFT Funds
Proposal Only Roposal and Plans Proposal only, plans	are separa	te		
For Local Public Agency: For a County and Road District Project		For a	Municipal Pro	ject
Submitted/Approved		Submitte	ed/Approved/P	assed
Highway Commissioner Signature & Date	Signatu	re & Date		
Scott Weaver Date: 2025.02.21 07:49:21 -06'00'				
	Official	Title		
Submitted/Approved				
County Engineer/Superintendent of Highways Signature & Date				
Digitally signed by Dan Parr				
Dan Parr Date: 2025.02.21 07:49:37 -06'00'		Departm	ent of Transp	ortation
Dan Parr Date: 2025.02.21 07:49:37		Released for	bid based on li	
Dan Parr Date: 2025.02.21 07:49:37	Regiona	-	bid based on li	
Dan Parr Date: 2025.02.21 07:49:37	Regiona	Released for	bid based on li	
Dan Parr Date: 2025.02.21 07:49:37	Regiona	Released for	bid based on li	

Note: All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed.

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
Washington Road District	Tazewell	25-19000-01-GM(N-MFT	TR 15-D/Guth Rd. & TR 21/Irisł

	NOTICE TO BIDDERS		
Sealed proposals for the pro	bject described below will be received at the office of $\frac{T}{T}$	ne Tazewell County Engir	neer
		Name of Of	fice
21308 Illinois Route 9	Tremont, Illinois 61568	_{until} 1:30 PM	_{on} 03/13/25
	Address	Time	Date
Sealed proposals will be op	ened and read publicly at the office of The Tazewell	County Engineer	
		Name of Office	
21308 Illinois Route 9	Tremont, Illinois 61568	_{at} 1:30 PM	_{on} 03/13/25
	Address	Time	Date
	DESCRIPTION OF WORK		
Location			Project Length
TR 15-D/ Guth Rd. & 1	R 21/ Irish Ln.		15,750 LF
Proposed Improvement			
	HMA SC IL-9.5 C N30, INCIDENTAL HMA SU	JRF and related work	
1. Plans and proposal form	s will be available in the office of		
Tazewell County High	way Engineer		
21308 Illinois Route 9			
Tremont IL,61568			
2. X Prequalification			
triplicate, showing all u	ent as read low bidders must file within 24 hours after th noompleted contracts awarded to them and all low bids priginal shall be filed with the Awarding Authority and tw	pending award for Federal, Sta	ate, County, Municipal
	reserves the right to waive technicalities and to reject a equirements and Conditions for Contract Proposals.	any or all proposals as provide	d in BLRS Special

- 4. The following BLR Forms shall be returned by the bidder to the Awarding Authority:
 - a. Local Public Agency Formal Contract Proposal (BLR 12200)
 - b. Schedule of Prices (BLR 12201)
 - c. Proposal Bid Bond (BLR 12230) (if applicable)
 - d. Apprenticeship or Training Program Certification (BLR 12325) (do not use for project with Federal funds.)
 - e. Affidavit of Illinois Business Office (BLR 12326) (do not use for project with Federal funds)
- 5. The quantities appearing in the bid schedule are approximate and are prepared for the comparison of bids. Payment to the Contractor will be made only for the actual quantities of work performed and accepted or materials furnished according to the contract. The scheduled quantities of work to be done and materials to be furnished may be increased, decreased or omitted as hereinafter provided.
- 6. Submission of a bid shall be conclusive assurance and warranty the bidder has examined the plans and understands all requirements for the performance of work. The bidder will be responsible for all errors in the proposal resulting from failure or neglect to conduct an in depth examination. The Awarding Authority will, in no case, be responsible for any costs, expenses, losses or changes in anticipated profits resulting from such failure or neglect of the bidder.
- 7. The bidder shall take no advantage of any error or omission in the proposal and advertised contract.
- 8. If a special envelope is supplied by the Awarding Authority, each proposal should be submitted in that envelope furnished by the Awarding Agency and the blank spaces on the envelope shall be filled in correctly to clearly indicate its contents. When an envelope other than the special one furnished by the Awarding Authority is used, it shall be marked to clearly indicate its contents. When sent by mail, the sealed proposal shall be addressed to the Awarding Authority at the address and in care of the official in whose office the bids are to be received. All proposals shall be filled prior to the time and at the place specified in the Notice to Bidders. Proposals received after the time specified will be returned to the bidder unopened.
- 9. Permission will be given to a bidder to withdraw a proposal if the bidder makes the request in writing or in person before the time for opening proposals.

Agency	County	Section Number	Route(s) (Street/Road Name)
on Road District	Tazewell	25-19000-01-GM(N-MFT	TR 15-D/Guth Rd. & TR 21/Ir
	PRO	POSAL	
l of			
		Contractor's Name	
	Contracto	r's Address	
s for the proposed work are t	those prepared by the Taz	ewell County Highway D	epartment
oved by the Department of T	ransportation on N/A		
	Construction" and the " Supp	Department of Transportation a Demental Specifications and R	and designated as "Standard Recurring Special Provisions" thereto,
ersigned agrees to accept, a g Special Provisions" contai		pplicable Special Provisions in	dicated on the "Check Sheet for
ersigned agrees to complete ed in accordance with the spe		working days or by 09/0	1/25 unless additional tir
	not required, the proposal g	uaranty check will be held in li	esit a contract bond for the full amoun eu thereof. If this proposal is accepte eed that the Bid Bond of check shall b
price multiplied by the quanti	ty, the unit price shall gover	n. If a unit price is omitted, the	a discrepancy between the products e total price will be divided by the price nor a total price is shown.
ersigned submits herewith th	ne schedule of prices on BL	R 12201 covering the work to	be performed under this contract.
			ombinations on BLR 12201, the work becified in the Schedule for Multiple B
al guaranty in the proper an	nount, as specified in BLRS	Special Provision for Bidding	Requirements and Conditions for
nd, if allowed, on Departmen	t form BLR 12230 or a prop	osal guaranty check, complyir	ng with the specifications, made paya
ount of the check is			(
nd, i shin	f allowed, on Departmen gton Township Supe	f allowed, on Department form BLR 12230 or a prop gton Township Supervisor, Jim Bremner,	

Attach Cashier's Check or Certified Check Here

In the event that one proposal guaranty check is intended to cover two or more bid proposals, the amount must be equal to the sum of the proposal guaranties which would be required for each individual bid proposal. If the proposal guaranty check is placed in another bid proposal, state below where it may be found.

The proposal guaranty check will be found in the bid proposal for: Section Number

_ .

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
Washington Road District	Tazewell	25-19000-01-GM(N-MFT	TR 15-D/Guth Rd. & TR 21/Irisł

CONTRACTOR CERTIFICATIONS

The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder.

- 1. **Debt Delinquency.** The bidder or contractor or subcontractor, respectively, certifies that it is not delinquent in the payment of any tax administered by the Department of Revenue unless the individual or other entity is contesting, in accordance with the procedure established by the appropriate Revenue Act, its liability for the tax or the amount of the tax. Making a false statement voids the contract and allows the Department to recover all amounts paid to the individual or entity under the contract in a civil action.
- 2. **Bid-Rigging or Bid Rotating**. The bidder or contractor or subcontractor, respectively, certifies that it is not barred from contracting with the Department by reason of a violation of either 720 ILCS 5/33E-3 or 720 ILCS 5/33E-4.

A violation of section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense, or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent on behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State of Local government. No corporation shall be barred from contracting with any unit of State or Local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent on behalf of the corporation.

- 3. **Bribery.** The bidder or contractor or subcontractor, respectively, certifies that, it has not been convicted of bribery or attempting to bribe an officer or employee of the State of Illinois or any unit of local government, nor has the firm made an admission of guilt of such conduct which is a matter or record, nor has an official, agent, or employee of the firm committed bribery or attempted bribery on behalf of the firm and pursuant to the direction or authorization of a responsible official of the firm.
- 4. **Interim Suspension or Suspension.** The bidder or contractor or subcontractor, respectively, certifies that it is not currently under a suspension as defined in Subpart I of Title 44 Subtitle A Chapter III Part 6 of the Illinois Administrative code. Furthermore, if suspended prior to completion of this work, the contract or contracts executed for the completion of this work may be canceled.

Local Public Agency	County	Section Num	nber	Route(s) (Street	/Road Name)		
Washington Road District	Tazewell	25-19000-0)1-GM(N-MFT	TR 15-D)/Guth	h Rd. & TR 21/Irish		
		GIGNATURES						
(If an individual)		Bidder Signature & Date						
		Business Addres	S					
		City			tate	Zip Code		
					lale			
						J		
(If a partnership)		Firm Name						
		Signature & Date						
		Title						
		Business Addres	S					
						7. 0. 1		
		City			tate	Zip Code		
la sattles Newser and Addamson of	- II Danta and							
Insert the Names and Addresses of	all Partners							
(If a corporation)		Corporate Name	!					
		Signature & Date	<u>}</u>					
		Title						
		Business Addres	s					
		City		S	tate	Zip Code		
In	sert Names of Officers	President						

Secretary

Attest:

Treasurer

Secretary





Contractor's Name

Contractor's Address	City			State	Zip Code
Local Public Agency		County	Se	ction Nun	nber
Washington Road District		Tazewell	25	-19000-0	01-GM(N-MFT)
Route(s) (Street/Road Name)					
TR 15-D/Guth Rd. and TR 21/Irish Lane					

Schedule for Multiple Bids

Combination Letter	Section Included in Combinations	Total

Schedule for Single Bid

(For complete information covering these items, see plans and specifications.)

Item Number	Items	Unit	Quantity	Unit Price	Total
1	HMA SURF REM BUTT JT	SQ YD	444		
2	P BIT MATLS TACK CT	POUND	50,400		
3	HMA BC IL-9.5 N30	TON	1,470		
4	HMA SC IL-9.5 C N30	TON	2,940		
5	INCIDENTAL HMA SURF	TON	17		
6	TRAF CONT & PROT SPL	L SUM	1		
	Bidder's Total Proposal				

- 1. Each pay item should have a unit price and a total price.
- 2. If no total price is shown or if there is a discrepancy between the product of the unit price multiplied by the quantity, the unit price shall govern.
- 3. If a unit price is omitted, the total price will be divided by the quantity in order to establish a unit price.
- 4. A bid may be declared unacceptable if neither a unit price or total price is shown.





For the Letting of 03/13/25

Bureau of Construction 2300 South Dirksen Parkway/Room 322 Springfield, IL 62764 Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

Part I. Work Under Contract

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

	1	2	3	4	Awards Pending	Accumulated Totals
Contract Number						
Contract With						
Estimated Completion Date						
Total Contract Price						
Uncompleted Dollar Value if Firm is the Prime Contractor						
Uncompleted Dollar Value if Firm is the Subcontractor						
Total Value of All Work						

Part II. Awards Pending and Uncompleted Work to be done with your own forces.

List below the uncompleted dollar value of work for each contract and awards pending to be completed with your own forces. All work subcontracted to others will be listed on the reverse of this form. In a joint venture, list only that portion of the work to be done by your company. If no work is contracted, show NONE.

· · · ·			
Earthwork			
Portland Cement Concrete Paving			
HMA Plant Mix			
HMA Paving			
Clean & Seal Cracks/Joints			
Aggregate Bases, Surfaces			
Highway, R.R., Waterway Struc.			
Drainage			
Electrical			
Cover and Seal Coats			
Concrete Construction			
Landscaping			
Fencing			
Guardrail			
Painting			
Signing			
Cold Milling, Planning, Rotomilling			
Demolition			
Pavement Markings (Paint)			
Other Construction (List)			
Totals			

Disclosure of this information is REQUIRED to accomplish the statutory purpose as outlined in the "Illinois Procurement Code." Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

Part III. Work Subcontracted to Others.

For each contract described in Part I, list all the work you have subcontracted to others.

	1	2	3	4	Awards Pending
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					

Total Uncompleted

Notary

I, being duly sworn, do hereby declare this affidavit is a true and correct statement relating to ALL uncompleted contracts of the undersigned for Federal, State, County, City and private work, including ALL subcontract work, ALL pending low bids not yet awarded or rejected and ALL estimated completion dates.

Officer or Director	
Title	
Signature	Date
Company	
Address	
City	State Zip Code

Subscribed and sworn to before me this day of,
(Signature of Notary Public) My commission expires
(Notary Seal)

Add pages for additional contracts



Local Public Agency Proposal Bid Bond

Local Public Agency	County	Section Number
Washington Road District	Tazewell	25-19000-01-GM(N-MFT)
WE,		as PRINCIPAL and

as SURETY, are held jointly,

severally and firmly bound unto the above Local Public Agency (hereafter referred to as "LPA") in the penal sum of 5% of the total bid price, or for the amount specified in the proposal documents in effect on the date of invitation for bids, whichever is the lesser sum. We bind ourselves, our heirs, executors, administrators, successors, and assigns, jointly pay to the LPA this sum under the conditions of this instrument.

WHEREAS THE CONDITION OF THE FOREGOING OBLIGATION IS SUCH that, the said PRINCIPAL is submitting a written proposal to the LPA acting through its awarding authority for the construction of the work designated as the above section.

THEREFORE if the proposal is accepted and a contract awarded to the PRINCIPAL by the LPA for the above designated section and the PRINCIPAL shall within fifteen (15) days after award enter into a formal contract, furnish surety guaranteeing the faithful performance of the work, and furnish evidence of the required insurance coverage, all as provided in the "Standard Specifications for Road and Bridge Construction" and applicable Supplemental Specifications, then this obligation shall become void; otherwise it shall remain in full force and effect.

IN THE EVENT the LPA determines the PRINCIPAL has failed to enter into a formal contract in compliance with any requirements set forth in the preceding paragraph, then the LPA acting through its awarding authority shall immediately be entitled to recover the full penal sum set out above, together with all court costs, all attorney fees, and any other expense of recovery.

IN TESTIMONY WHEREOF, the said PRINCIPAL and the said SURETY have caused this instrument to be signed by their respective officers this of

Day Mont	h and Year Principal
Company Name	Company Name
Signature & Date	Signature & Date
By:	By:
Title	Title
(If Principal is a joint venture of two or more contract affixed.)	ors, the company names, and authorized signatures of each contractor must be
,	Surety
Name of Surety	Signature of Attorney-in-Fact Signature & Date
	By:
STATE OF IL	
COUNTY OF	
Ι	, a Notary Public in and for said county do hereby certify that
(Insert names of i	ndividuals signing on behalf of PRINCIPAL & SURETY)
	e persons whose names are subscribed to the foregoing instrument on behalf of
	day in person and acknowledged respectively, that they signed and delivered said
Given under my hand and notarial seal this	day of Nay Month and Year
	Notary Public Signature & Date
(SEAL, if required by the LPA)	
	Date commission expires

Local Public Agency	County	Section Number
Washington Road District	Tazewell	25-19000-01-GM(N-MFT)

ELECTRONIC BID BOND

Electronic bid bond is allowed (box must be checked by LPA if electronic bid bond is allowed)

The Principal may submit an electronic bid bond, in lieu of completing the above section of the Proposal Bid Bond Form. By providing an electronic bid bond ID code and signing below, the Principal is ensuring the identified electronic bid bond has been executed and the Principal and Surety are firmly bound unto the LPA under the conditions of the bid bond as shown above. (If PRINCIPAL is a joint venture of two or more contractors, an electronic bid bond ID code, company/Bidder name title and date must be affixed for each contractor in the venture.)

Electronic Bid Bond ID Code

Company/Bidder Name

Signature & Date

Title



Apprenticeship and Training Program Certification

Local Public Agency	County	Street Name/Road Name	Section Number
Washington Road District	Tazewell	TR 15-D & TR 21	25-19000-01-GM(N-MFT)

All contractors are required to complete the following certification

For this contract proposal or for all bidding groups in this deliver and install proposal.

For the following deliver and install bidding groups in this material proposal.

Illinois Department of Transportation policy, adopted in accordance with the provisions of the Illinois Highway Code, requires this contract to be awarded to the lowest responsive and responsible bidder. The award decision is subject to approval by the Department. In addition to all other responsibility factors, this contract or deliver and install proposal requires all bidders and all bidder's subcontractors to disclose participation in apprenticeship or training programs that are (1) approved by and registered with the United States Department of Labor's Bureau of Apprenticeship and Training, and (2) applicable to the work of the above indicated proposals or groups. Therefore, all bidders are required to complete the following certification:

1. Except as provided in paragraph 4 below, the undersigned bidder certifies that it is a participant, either as an individual or as part of a group program, in an approved apprenticeship or training program applicable to each type of work or craft that the bidder will perform with its own employees.

2. The undersigned bidder further certifies, for work to be performed by subcontract, that each of its subcontractors either (A) is, at the time of such bid, participating in an approved, applicable apprenticeship or training program; or (B) will, prior to commencement of performance of work pursuant to this contract, establish participation in an approved apprenticeship or training program applicable to the work of the subcontract.

3. The undersigned bidder, by inclusion in the list in the space below, certifies the official name of each program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's employees. Types of work or craft that will be subcontracted shall be included and listed as subcontract work. The list shall also indicate any type of work or craft job category for which there is no applicable apprenticeship or training program available.

4. Except for any work identified above, if any bidder or subcontractor shall perform all or part of the work of the contract or deliver and install proposal solely by individual owners, partners or members and not by employees to whom the payment of prevailing rates of wages would be required, check the following box, and identify the owner/operator workforces and positions of ownership.

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project is accounted for and listed. The Department at any time before or afterward may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. In order to fulfill the participation requirement, it shall not be necessary that any applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract or deliver and install proposal.

Bidder		Signature & Date		
Title				
Address	City		State	Zip Code



Affidavit of Illinois Business Office

Local Public Agency	County	Stree	t Name/Road Name	Sect	ion Number
Washington Road District	Tazewell	TR 1	5-D & TR 21	25-1	9000-01-GM(N-MFT)
1	of				
I,Name of Affiant	0	City c	of Affiant	's	, tate of Affiant
being first duly sworn upon oath, state as follows:		,			
1. That I am the	of				
Officer or Position			Bidder		
2. That I have personal knowledge of the facts her	rein stated.				
3. That, if selected under the proposal described a	above,			, will maintain	a business office in the
		Bidde			
State of Illinois, which will be located in	County	County, Illinoi	IS.		
4. That this business office will serve as the prima	,	when the any	norsons omnloved	in the construct	tion contomplated by
this proposal.	ily place of emplo	by mention any	persons employed		ion contemplated by
5. That this Affidavit is given as a requirement of s	state law as provi	ded in Section	30-22(8) of the Illin	ois Procuremer	nt Code
			nature & Date		
		Prin	t Name of Affiant		
Notary Public					
State of IL					
County					
Signed (or subscribed or attested) before me on	(date)	by			
	(date)				
(nam	e/s of person/s)			, auth	orized agent(s) of
(1011)					
Bidder					
			Notary Public S	Signature & Da	te
(SEAL)			My commission	expires	

INDEX FOR SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS

Adopted January 1, 2025

This index contains a listing of SUPPLEMENTAL SPECIFICATIONS and frequently used RECURRING SPECIAL PROVISIONS.

ERRATA Standard Specifications for Road and Bridge Construction

(Adopted 1-1-22) (Revised 1-1-25)

SUPPLEMENTAL SPECIFICATIONS

Std. Spe	ec. Sec.	Page No.
202	Earth and Rock Excavation	1
204	Borrow and Furnished Excavation	2
207	Porous Granular Embankment	3
211	Topsoil and Compost	
406	Hot-Mix Asphalt Binder and Surface Course	
407	Hot-Mix Asphalt Pavement (Full-Depth)	7
420	Portland Cement Concrete Pavement	8
502	Excavation for Structures	9
509	Metal Railings	10
540	Box Culverts	
542	Pipe Culverts	31
550	Storm Sewers	
586	Granular Backfill for Structures	47
630	Steel Plate Beam Guardrail	
632	Guardrail and Cable Road Guard Removal	
644	High Tension Cable Median Barrier	50
665	Woven Wire Fence	
701	Work Zone Traffic Control and Protection	
781	Raised Reflective Pavement Markers	54
782	Reflectors	55
801	Electrical Requirements	57
821	Roadway Luminaires	60
1003	Fine Aggregates	
1004	Coarse Aggregates	
1010	Finely Divided Minerals	
1020	Portland Cement Concrete	
1030	Hot-Mix Asphalt	
1040	Drain Pipe, Tile, and Wall Drain	
1061	Waterproofing Membrane System	
1067	Luminaire	
1097	Reflectors	
1102	Hot-Mix Asphalt Equipment	78



Check Sheet for Recurring Special Provisions

Local Public Agency	County	Section Number
Washington Road District	Tazewell	25-19000-01-GM(N-MFT)

Check this box for lettings prior to 01/01/2025

The Following Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Che	<u>ck Sheet #</u>		<u>Page No</u>
1		Additional State Requirements for Federal-Aid Construction Contracts	79
2		Subletting of Contracts (Federal-Aid Contracts)	82
3		EEO	83
4		Specific EEO Responsibilities Non Federal-Aid Contracts	93
5		Required Provisions - State Contracts	98
6		Asbestos Bearing Pad Removal	104
7		Asbestos Waterproofing Membrane and Asbestos HMA Surface Removal	105
8		Temporary Stream Crossings and In-Stream Work Pads	106
9		Construction Layout Stakes	107
10		Use of Geotextile Fabric for Railroad Crossing	110
11		Subsealing of Concrete Pavements	112
12		Hot-Mix Asphalt Surface Correction	116
13		Pavement and Shoulder Resurfacing	118
14		Patching with Hot-Mix Asphalt Overlay Removal	119
15		Polymer Concrete	121
16		Reserved	123
17		Bicycle Racks	124
18		Temporary Portable Bridge Traffic Signals	126
19		Nighttime Inspection of Roadway Lighting	128
20		English Substitution of Metric Bolts	129
21		Calcium Chloride Accelerator for Portland Cement Concrete	130
22		Quality Control of Concrete Mixtures at the Plant	131
23		Quality Control/Quality Assurance of Concrete Mixtures	139
24		Reserved	155
25		Reserved	156
26		Temporary Raised Pavement Markers	157
27		Restoring Bridge Approach Pavements Using High-Density Foam	158
28		Portland Cement Concrete Inlay or Overlay	161
29		Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	165
30		Longitudinal Joint and Crack Patching	168
31		Concrete Mix Design - Department Provided	170
32		Station Numbers in Pavements or Overlays	171

Recurring Special Provisions

Local Public Agency	County	Section Number
Washington Road District	Tazewell	25-19000-01-GM(N-MFT)

The Following Local Roads And Streets Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Local Roads And Streets Recurring Special Provisions

Check Sheet # Page No.			
LRS 1		Reserved	173
LRS 2		Furnished Excavation	174
LRS 3	\boxtimes	Work Zone Traffic Control Surveillance	175
LRS 4	\boxtimes	Flaggers in Work Zones	176
LRS 5	\boxtimes	Contract Claims	177
LRS 6	\boxtimes	Bidding Requirements and Conditions for Contract Proposals	178
LRS 7		Bidding Requirements and Conditions for Material Proposals	184
LRS 8		Reserved	190
LRS 9		Bituminous Surface Treatments	191
LRS 10		Reserved	195
LRS 11	\boxtimes	Employment Practices	196
LRS 12	\boxtimes	Wages of Employees on Public Works	198
LRS 13	\boxtimes	Selection of Labor	200
LRS 14		Paving Brick and Concrete Paver Pavements and Sidewalks	201
LRS 15	\boxtimes	Partial Payments	204
LRS 16		Protests on Local Lettings	205
LRS 17	\boxtimes	Substance Abuse Prevention Program	206
LRS 18		Multigrade Cold Mix Asphalt	207
LRS 19		Reflective Crack Control Treatment	208

TABLE OF CONTENTS

Page 1	Bidding Requirements and Conditions Description of Work Traffic
Page 2	Traffic Control Plan Traffic Control Plan (Cont'd.) Hot-Mix Asphalt Binder Course Hot-Mix Asphalt Surface Course Substitution of Bituminous Mixtures
	Hot-Mix Asphalt Surface Removal- Butt Joint Incidental Hot-Mix Asphalt Surfacing
	Aggregate Shoulders
	Weight Limits
Page 3	General Notes
	Pre-Construction Meeting
	Time Schedule
	Wages of Employees on Public Works
Page 4-5	BDE Special Provisions Check Sheets
Page 6-19	BDE Special Provisions
Page 20-27	LR Special Provisions
Page 28	Project Location Map
Page 29	Quantity Sheet
Page 30	Typical Cross Sections
Page 31	Standard for HMA Surfacing at Sideroads, Entrances & Mailboxes
Page 32-34	Butt Joints
Page 35-43	Traffic Control Standards





Local Public Agency	County	Section Number
Washington Road District	Tazewell	25-19000-01-GM(N-MFT)

The following Special Provision supplement the "Standard Specifications for Road and Bridge Construction", adopted

January 1, 2022

, the latest edition of the "Manual on Uniform Traffic Control Devices for

Streets and Highways", and the "Manual of Test Procedures of Materials" in effect on the date of invitation of bids, and the Supplemental Specification and Recurring Special Provisions indicated on the Check Sheet included here in which apply to and govern the construction of the above named section, and in case of conflict with any parts, or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

<u>BIDDING REQUIREMENTS AND CONDITIONS</u>: Prequalification of bidders with the Illinois Department of Transportation is required.

DESCRIPTION OF WORK: The work of this section consists of Hot-Mix Asphalt Surface Removal- Butt Joint; Hot-Mix Asphalt Binder Course, IL-9.5, N30, Hot-Mix Asphalt Surface Course, IL-9.5, Mix "C", N30 and related operations on top of existing bituminous surfaces.

TRAFFIC: TR 15-D-Irish Lane and TR 21-Guth Road shall be closed for both local and through traffic during the following operations: Hot-Mix Asphalt Surface Removal - Butt Joint, Polymerized Bituminous Materials (Tack Coat), Hot-Mix Asphalt Binder Course, IL-9.5 N30 and Hot-Mix Asphalt Surface Course, IL-9.5, Mix "C", N30. The Washington Township Highway Commissioner shall be notified a minimum 48 hours in advance of the start of construction to properly notify the property owners along the construction improvement routes.

TRAFFIC CONTROL PLAN: Traffic Control shall be in accordance with the applicable sections of the "Standard Specifications for Road and Bridge Construction", the applicable guidelines contained in the "Manual on Uniform Traffic Control Devices for Streets and Highways", these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Articles 107.09 and 107.14 of the "Standard Specifications for Road and Bridge Construction" and the Traffic Control Standards 701006-05, 701011-04, 701201-05, 701301-04, 701306-04, 701901-10 and BLR 21-9 contained herein.

The presence of temporary traffic control drawings or standards in the proposal or contract, whether a pay item or not, does not relieve the Contractor of his obligation to the public. The Contractor shall provide, if conditions warrant by the Engineer, all protection deemed necessary beyond that shown in the proposal or Special Provisions.

"NO PASSING ZONES NOT STRIPED NEXT_____ MILES" signs shall be posted in accordance with Article 701.17.

Construction signs shall meet the current Standard Specifications for Traffic Control Items.

The Contractor shall be responsible for all traffic control operations as follows:

1. The Contractor shall provide one (1) flagger placed at the end of each construction route to control the traffic. Flaggers must hold the "Flagger Traffic Control Sign" (Stop/Slow paddle).

Local Public Agency	County	Section Number
Washington Road District	Tazewell	25-19000-01-GM(N-MFT)

The Road District shall be responsible for all traffic control operations as follows:

 The Washington Township Road District shall provide all traffic control signage/devices for each construction route pertaining to this project, except for ""NO PASSING ZONES NOT STRIPED NEXT______ MILES" signs.

Basis of payment: All required Traffic Control shall be paid for at the contract-lump sum price for TRAFFIC CONTROL & PROTECTION, (SPECIAL).

HOT-MIX ASPHALT BINDER COURSE: This work shall be constructed in accordance with Article 406 of the "Standard Specifications for Road and Bridge Construction" except that the minimum lift thickness shall be 0.5 inches at centerline for HOT-MIX ASPHALT BINDER COURSE IL 9.5 N30 as specified on the typical cross section elsewhere herein. The HOT-MIX ASPHALT BINDER COURSE IL 9.5 N30 shall be placed in a single pass at the full width specified in the plans.

HOT-MIX ASPHALT SURFACE COURSE: The HOT-MIX ASPHALT SURFACE COURSE IL 9.5 N30 shall be placed in a single pass at the full width specified in the plans.

SUBSTITUTION OF BITUMINOUS MIXTURES: Bituminous Mixtures of a higher quality may be substituted for the designs specified at the approval of the Engineer. The contractor shall provide the Engineer with an approved mix design at least 24 hours prior to its use for his review. Use of the proposed substitute mix shall be solely at the discretion of the Engineer. The new mixture will be measured and paid for under the same applicable articles as the mixture for which it is substituted.

HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT:

The surface removal shall be performed according to Article 406.08 and Section 440.

Revise Article 440.06 Disposal of Material to read as follows: All milled material will remain the property of the Washington Township Road District and shall be transported from the job site to the Washington Township Road District storage yard located at the intersection of Washington Rd and Cooper Road in Washington, Illinois. Other sites may be determined by mutual agreement between the Contractor and the Road District. If other sites are approved, the Contractor will be responsible for preventing theft of milled material or unauthorized removal of said material from sites other than Washington Township Road District property.

Add the following to Article 440.08 Basis of Payment: Hauling of milled material shall be included in the cost of HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT and no extra compensation will be allowed.

INCIDENTAL HOT-MIX ASPHALT SURFACING: The bituminous mixture shall be placed by hand directly in front of the paving operations as directed by the Engineer. Any preparation required prior to construction of INCIDENTAL HOT-MIX ASPHALT SURFACING will not be measured separately but shall be included in the contract unit price per ton for INCIDENTAL HOT-MIX ASPHALT SURFACING.

AGGREGATE SHOULDERS: Aggregate shoulders shall be constructed by others.

WEIGHT LIMITS: Legal weight limits shall be observed on Washington Road District roads and structures they contain at all times.

Local Public Agency	County	Section Number
Washington Road District	Tazewell	25-19000-01-GM(N-MFT)

<u>GENERAL NOTES</u>: Where section or subsection monuments are encountered, the Engineer shall be notified before such monuments are removed. The Contractor shall protect and carefully preserve all property markers and monuments until the owner, and authorized surveyor or agent has witnessed or otherwise referenced their location.

PRE-CONSTRUCTION MEETING: A pre-construction meeting for this Section is required between the Contractor, Highway Commissioner and the Resident Engineer.

TIME SCHEDULE: The specified completion date for this project is September 1, 2025.

WAGES OF EMPLOYEES ON PUBLIC WORKS: Add the following to paragraph #1 of the Special Provision for Wages of Employees on Public Works, Check Sheet LRS#12: Prevailing wage rates may be obtained from the IDOL (Illinois Department of Labor) website at:

https://www2.illinois.gov/idol/Laws-Rules/CONMED/Pages/Rates.aspx

BDE SPECIAL PROVISIONS For the January 17 and March 7, 2025 Lettings

The following special provisions indicated by a "check mark" are applicable to this contract and will be included by the Project Coordination and Implementation Section of the Bureau of Design & Environment (BDE).

80099 1 Accessible Pedestrian Signals (APS) April 1, 2022 Jan. 1, 2028 April 1, 2022 80172 2 Aggregate Subgrade Improvement April 1, 2022 April 1, 2023 80173 4 Bituminous Materials Cost Adjustments Nov. 2, 2006 Aug. 1, 2027 80241 6 Bituminous Surface Treatment with Fog Seal Jan. 1, 2022 Aug. 1, 2022 * 50531 7 Building Removal Sept. 1, 1990 Aug. 1, 2022 * 60261 7 Building Removal Sept. 1, 1990 Aug. 1, 2022 80460 9 Compensable Delay Costs June 2, 2017 April 1, 2008 80198 11 Completion Date (via calendar days) April 1, 2008 April 1, 2008 80461 13 Concrete Barrier Nov. 1, 2025 Sedt3 June 1, 2010 Jan. 1, 2025 80451 15 Construction Air Quality – Diseal Retrofit June 1, 2003 June 1, 2003 804261 15 Construction Air Quality – Diseal Retrofit June 1, 2003 June 1, 2023 804452 16 Disadvantaged B	File	e Name	#		Special Provision Title	Effective	Revised
802742Aggregate Subgrade ImprovementApril 1, 2012April 1, 2023801923Automated Flagger Assistance DevicesJan. 1, 2020Aug. 1, 2017801734Bituminous Materials Cost AdjustmentsNov. 2, 2006Aug. 1, 2017802425Bituminous Surface Treatment with Fog SealJuly 1, 2009July 1, 2009*802416Bridge Demolition DebrisJuly 1, 2009*505317Building RemovalSept. 1, 1990Aug. 1, 2022804609Cement, Finely Divided Minerals, Admixtures, Concrete, and MortarJan. 1, 20258038410XCompletion Date (via calendar days)April 1, 20088046111Concrete BarrierJan. 1, 20258045112Concrete GarrierJan. 1, 20258045113Concrete BarrierJan. 1, 20258045114Concrete BarrierJan. 1, 20268029116Disadvantaged Business Enterprise ParticipationSept. 1, 20008022916Disadvantaged Business Enterprise ParticipationApril 1, 20138045218Full Lane Sealent Waterproofing SystemNov. 1, 20238044719Grading and Shaping) DitchesJan. 1, 20248044621KHot-Mix AsphaltLongitudinal Joint Sealant8045212Hot-Mix Asphalt Partement MarkingJan. 1, 20248045323Illinois Works Apprenticeship Initiative – State Funded ContractsJune 1, 20248045424Preforman	<u>1 II</u>						
80192 3 Automated Flagger Assistance Devices Jan. 1, 2008 April 1, 2023 80173 4 Bituminous Materials Cost Adjustments Nov. 2, 2006 Aug. 1, 2017 80426 5 Bituminous Surface Treatment with Fog Seal Jan. 1, 2020 Jan. 1, 2022 80241 6 Bridge Demolition Debris July 1, 2009 Aug. 1, 2022 80460 9 Cement, Finely Divided Minerals, Admixtures, Concrete, and Mortar Jan. 1, 2025 Rost April 1, 2019 80198 11 Completion Date (via calendar days) April 1, 2008 April 1, 2008 80419 12 Completion Date (via calendar days) April 1, 2008 April 1, 2008 80418 13 Concrete Barrier Nov. 1, 2023 Marc 2, 2017 80421 15 Construction Air Quality – Diesel Retrofit June 1, 2010 Jan. 1, 2025 80422 17 Fuel Cost Adjustment April 1, 2023 April 1, 2023 80447 19 Green Preformed Thermoplastic Pavement Markings Jan. 1, 2022 Jan. 1, 2023 80445 12 Hot-Mix Asphalt				H			
80173 4 Bituminous Materials Cost Adjustments Nov. 2, 2006 Aug. 1, 2017 80246 5 Bituminous Surface Treatment with Fog Seal Jan. 1, 2022 Jan. 1, 2022 80241 6 Bridge Demolition Debris July 1, 2009 Aug. 1, 2022 50261 8 Building Removal Sept. 1, 1990 Aug. 1, 2022 80460 9 Cement, Finely Divided Minerals, Admixtures, Concrete, and Mortar Jan. 1, 2025 80384 10 Complesion Date (via calendar days) April 1, 2008 80460 9 Completion Date (via calendar days) April 1, 2008 80481 11 Concrete Sealer Jan. 1, 2025 80461 12 Concrete Sealer Nov. 1, 2023 80261 15 Construction Air Quality – Diesel Retrofit Jun. 1, 2024 Jan. 1, 2025 80262 16 Disadvantaged Business Enterprise Participation Sept. 1, 2000 Aug. 1, 2017 80452 11 Lane Sealant Waterproofing System Nov. 1, 2023 80447 19 Grading and Shaping Ditches Jaan. 1, 2024<				H			
80426 5 Bitluminous Surface Treatment with Fog Seal Jan. 1, 2020 Jan. 1, 2022 80426 Bridge Demolition Debris July 1, 2009 July 1, 2009 50531 7 Building Removal Sept. 1, 1990 Aug. 1, 2022 80460 9 Cement, Finely Divided Minerals, Admixtures, Concrete, and Mortal Jan. 1, 2025 80384 10 Compensable Delay Costs June 2, 2017 April 1, 2008 80198 11 Completion Date (via calendar days) Plus Working Days April 1, 2008 80461 13 Concrete Barrier Nov. 1, 2023 80261 15 Construction Air Quality – Diesel Retrofit June 1, 2010 Jan. 1, 2025 80251 16 Disadvantaged Business Enterprise Participation Sept. 1, 2000 Mar. 2, 2019 80452 18 Full Lane Sealant Waterproofing System Nov. 1, 2023 Jan. 1, 2024 Jan. 1, 2024 80447 19 Grading and Shaping Ditches Jan. 1, 2024 Jan. 1, 2024 Jan. 1, 2024 80445 24 Mot-Mix Asphait Longritudinal Joint Sealant Nov. 1, 2023				H			
 * 80241 6 Bridge Demolition Debris Sopti 1, 1990 Sopti 1, 1990 Aug. 1, 2022 Sopti 1, 1990 Aug. 1, 2022 Sopti 1, 1990 Aug. 1, 2022 Sopti 1, 1990 Compensable Delay Costs Song 12 Completion Date (via calendar days) Bollion Date (via calendareling Malin Date (via calendar days) Bollion Date				H			
* 50531 7 Building Removal Sept. 1, 1990 Aug. 1, 2022 * 50261 8 Building Removal with Asbestos Abatement Sept. 1, 1990 Aug. 1, 2022 80460 9 Cement, Finely Divided Minerals, Admixtures, Concrete, and Mottar Jan. 1, 2025 80384 10 X Completion Date (via calendar days) April 1, 2008 * 80199 12 Completion Date (via calendar days) Plus Working Days April 1, 2008 * 80193 14 Concrete Barrier Jan. 1, 2023 80261 15 Concrete Barrier Jan. 1, 2023 80261 15 Concrete Saelar Nov. 1, 2023 80261 15 Consdutaged Business Enterprise Participation Sept. 1, 2009 Aug. 1, 2017 80452 18 Full Lane Sealant Waterproofing System Nov. 1, 2023 Bod456 Jan. 1, 2024 Jan. 1, 2024 Jan. 1, 2025 80452 10 Hot-Mix Asphati Longitudinal Joint Sealant Nov. 1, 2023 Aug. 1, 2022 Aug. 1, 2024 April 2, 2024 80452 21 Hot-Mix Asphat				Ц	•		Jan. 1, 2022
* 50261 8 Building Removal with Asbestos Abatement Sept. 1, 1990 Aug. 1, 2022 80364 10 Compensable Delay Costs June 2, 2017 April 1, 2008 * 80198 11 Completion Date (via calendar days) April 1, 2008 April 1, 2008 * 80199 12 Completion Date (via calendar days) April 1, 2008 April 1, 2008 * 80461 13 Concrete Barrier June 1, 2025 April 1, 2009 80261 15 Construction Air Quality – Diesel Retrofit June 1, 2020 Mar. 2, 2019 80229 16 Disadvantaged Business Enterprise Participation Sept. 1, 2000 Mar. 2, 2019 80447 19 Grading and Shaping Ditches Jan. 1, 2023 Jan. 1, 2024 Jan. 1, 2024 80446 21 Hot-Mix Asphalt Jan. 1, 2024 Jan. 1, 2024 Jan. 1, 2024 80445 21 Hot-Mix Asphalt John Mar. 2, 2024 April 2, 2024 80445 22 Hot-Mix Asphalt Jan. 1, 2023 April 2, 2024 80445 24 Hot-Mix Asphalt John Nov. 1, 2023 April 2, 2024				Ц			
80460 9 Cement, Finely Divided Minerals, Admixtures, Concrete, and Mortar Jan. 1, 2025 80384 10 Compensable Delay Costs June 2, 2017 April 1, 2019 80198 11 Completion Date (via calendar days) April 1, 2008 April 1, 2008 80199 12 Concrete Barrier Jan. 1, 2025 April 1, 2010 80451 13 Concrete Sealer Nov. 1, 2023 80261 15 Concrete Sealer Nov. 1, 2023 80229 17 Fuel Cost Adjustment April 1, 2009 Aug. 1, 2017 80452 18 Fuel Cost Adjustment April 1, 2023 Aug. 1, 2023 80445 19 Grading and Shaping Ditches Jan. 1, 2024 Jan. 1, 2022 80453 20 Green Preformed Thermoplastic Pavement Markings Jan. 1, 2024 Jan. 1, 2022 80446 22 Hot-Mix Asphalt - Longitudinal Joint Sealant Nov. 1, 2022 Aug. 1, 2023 80445 23 Illinois Works Apprenticeship Initiative – State Funded Contracts June 2, 2021 April 2, 2024 80455 26 Preformed Plastic Pavement Marking Jan. 1, 2022 April 2, 2024				Ц		•	
80384 10 Image: Compensable Delay Costs June 2, 2017 April 1, 2019 * 80198 11 Completion Date (via calendar days) Plus Working Days April 1, 2008 April 1, 2008 80461 13 Concrete Barrier Jan. 1, 2025 April 1, 2009 80453 14 Concrete Barrier Jan. 1, 2025 Mov. 1, 2023 80259 16 Disadvantaged Business Enterprise Participation Sept. 1, 2009 Mar. 2, 2019 80229 17 Fuel Cost Adjustment April 1, 2003 Aug. 1, 2017 80447 19 Grading and Shaping Ditches Jan. 1, 2022 Jan. 1, 2022 80456 21 Hot-Mix Asphalt Jan. 1, 2024 Jan. 1, 2022 80446 22 Hot-Mix Asphalt Jan. 1, 2024 Jan. 1, 2023 80445 23 Illinois Works Apprenticeship Initiative - State Funded Contracts June 2, 2021 April 2, 2024 80450 24 Mechanically Stabilized Earth Retaining Walls Aug. 1, 2023 April 2, 2024 80450 26 Preformach Graded Asphalt Binder Jan. 1, 2024 April 2, 2024 80455 28 Removal and Disposal of	*			Ц			Aug. 1, 2022
 * 80198 11 Completion Date (via calendar days) * 80199 12 Completion Date (via calendar days) Plus Working Days * 80199 12 Concrete Barrier * 80193 13 Concrete Sealer * 80261 13 Concrete Sealer * 80221 15 Construction Air Quality – Diesel Retrofit * 80229 16 Disadvantaged Business Enterprise Participation * 80229 17 Fuel Cost Adjustment * 80229 17 Fuel Cost Adjustment * 80219 8 Concrete Sealer * 80229 17 Fuel Cost Adjustment * 80229 17 Fuel Cost Adjustment * 80219 18 Concrete Sealer * 80229 17 Fuel Cost Adjustment * 80219 18 Concrete Sealer * 80453 20 Green Preformed Thermoplastic Pavement Markings * 90452 21 Mot-Mix Asphalt * 104-Mix Asphalt 				Ц			
* 80199 12 Completion Date (via calendar days) Plus Working Days April 1, 2008 80461 13 Concrete Sealer Nov. 1, 2023 80261 15 Construction Air Quality – Diesel Retrofit June 1, 2010 Jan. 1, 2025 80293 16 Disadvantaged Business Enterprise Participation Sept. 1, 2000 Mar. 2, 2019 80229 17 Fuel Cost Adjustment April 1, 2009 Aug. 1, 2017 80452 18 Fuel Cost Adjustment Nov. 1, 2023 80447 19 Grading and Shaping Ditches Jan. 1, 2024 Jan. 1, 2022 80436 21 Hot-Mix Asphalt Jan. 1, 2024 Jan. 1, 2022 80446 22 Hot-Mix Asphalt Jan. 1, 2024 Jan. 1, 2024 80447 25 Performed Construction and Saphalt Bindier June 2, 2024 April 2, 2024 80448 22 Hot-Mix Asphalt - Longitudinal Joint Sealant Nov. 1, 2023 Aug. 1, 2023 80445 29 Performmed Craded Asphalt Bindier Jan. 1, 2024 April 2, 2024 80459 26 Preformed Plastic Pavement Marking Jan. 1, 2024 April 2, 2024 <td></td> <td></td> <td></td> <td>M</td> <td></td> <td></td> <td>April 1, 2019</td>				M			April 1, 2019
80461 13 Concrete Barrier Jan. 1, 2025 80453 14 Concrete Sealer Nov. 1, 2023 80261 15 Construction Air Quality – Diesel Retrofit Jun. 1, 2010 Jan. 1, 2025 * 80029 16 Disadvantaged Business Enterprise Participation Sept. 1, 2000 Mar. 2, 2019 80229 17 Fuel Cost Adjustment April 1, 2023 Mar. 2, 2019 80447 19 Grading and Shaping Ditches Jan. 1, 2023 Jan. 1, 2024 Jan. 1, 2024 Jan. 1, 2022 80448 22 Hot-Mix Asphalt Jan. 1, 2024 Jan. 1, 2022 Jan. 1, 2022 80448 22 Hot-Mix Asphalt Longitudinal Joint Sealant Nov. 1, 2023 April 2, 2024 80450 24 HochMix Asphalt Elaning Walls Aug. 1, 2023 April 2, 2024 April 2, 2024 80455 28 Removal and Disposal of Regulated Substances Jan. 1, 2022 April 2, 2024 * 34261 Terformed Plastic Pavement Markings April 1, 2024 April 2, 2024 * 34261 Seedin						April 1, 2008	
8045314Concrete SealerNov. 1, 20238026115Construction Air Quality – Diesel RetrofitJune 1, 2010Jan. 1, 20258002916Disadvantaged Business Enterprise ParticipationSept. 1, 2000Mar. 2, 20198022917Fuel Cost AdjustmentApril 1, 2009Aug. 1, 20178045218Full Lane Sealant Waterproofing SystemNov. 1, 20238044320Grading and Shaping DitchesJan. 1, 2021Jan. 1, 20228044320Green Preformed Thermoplastic Pavement MarkingsJan. 1, 2024Jan. 1, 20258044622Hot-Mix AsphaltJan. 1, 2024Jan. 1, 2024Jan. 1, 20258044323Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 2024April 2, 20248045024Mechanically Stabilized Earth Retaining WallsAug. 1, 2023April 2, 20248045125Preformace Graded Asphali BinderJan. 1, 2023Jan. 1, 20228045226Preformed Plastic Pavement MarkingJune 2, 2024April 1, 2024* 3426127Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528XRemoval and Disposal of Regulated SubstancesJan. 1, 2025April 2, 20248044631Sign Panels and AppurtenancesJan. 1, 2025April 2, 20248044529Source of Supply and Quality RequirementsJan. 1, 2025April 2, 20148044531Sign Panels and AppurtenancesJan. 1, 2025April 2	*				Completion Date (via calendar days) Plus Working Days	April 1, 2008	
8026115Construction Air Quality – Diesel RetrofitJune 1, 2010Jan. 1, 2025*8002916Disadvantaged Business Enterprise ParticipationSept. 1, 2009Mar. 2, 20198042218Fuel Cost AdjustmentApril 1, 2009Aug. 1, 20178045218Full Lane Sealant Waterproofing SystemNov. 1, 20238044719Grading and Shaping DitchesJan. 1, 2021Jan. 1, 20228045320Green Preformed Thermoplastic Pavement MarkingsJan. 1, 2024Jan. 1, 20228044621Hot-Mix AsphaltLongitudinal Joint SealantNov. 1, 2022Aug. 1, 20238044823Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 2024April 2, 20248045024Mechanically Stabilized Earth Retaining WallsAug. 1, 2023April 2, 20248045025Preformance Graded Asphalt BinderJan. 1, 2024April 1, 20248045026Preformed Plastic Pavement MarkingJune 2, 2024April 1, 2024* 3426127Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528XRemoval and Disposal of Regulated SubstancesJan. 1, 2024April 2, 20248044530Short Term and Temporary Pavement MarkingsApril 2, 2024April 2, 20248044531Sign Panels and AppurtenancesJan. 1, 2022April 2, 20248044533Speed Display TrailerApril 2, 2014Jan. 1, 20228044534Source of		80461	13		Concrete Barrier	Jan. 1, 2025	
*8002916Disadvantaged Business Enterprise ParticipationSept. 1, 2000Mar. 2, 20198022917Fuel Cost AdjustmentApril 1, 2009Aug. 1, 20178045218Full Lane Sealant Waterproofing SystemNov. 1, 20238044719Grading and Shaping DitchesJan. 1, 20238043320Green Preformed Thermoplastic Pavement MarkingsJan. 1, 20248045621Hot-Mix AsphaltJan. 1, 20228045822Hot-Mix Asphalt - Longitudinal Joint SealantNov. 1, 20228044823Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 20218045024Mechanically Stabilized Earth Retaining WallsAug. 1, 20238045125Performed Plastic Pavement MarkingJune 2, 20248045526Preformed Plastic Pavement MarkingJune 2, 20248045528Removal and Disposal of Regulated SubstancesJan. 1, 20228045730Short Term and Temporary Pavement MarkingsApril 1, 20248046231Sign Panels and AppurtenancesJan. 1, 20228044632Source of Supply and Quality RequirementsJan. 2, 20148039136Subcontractor Mobilization Payment ReportingApril 2, 20148039737Subcontractor Mobilization PaymentsNov. 2, 20178039736Subcontractor Mobilization PaymentsNov. 2, 20178039131Subcontractor Mobilization PaymentsNov. 2, 20148039339Training Spe		80453	14		Concrete Sealer	Nov. 1, 2023	
8022917Fuel Cost AdjustmentApril 1, 2009Aug. 1, 20178045218Full Lane Sealant Waterproofing SystemNov. 1, 20238044719Grading and Shaping DitchesJan. 1, 20238043320Green Preformed Thermoplastic Pavement MarkingsJan. 1, 20218045621XHot-Mix AsphaltJan. 1, 20248043823Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 20218045024Mechanically Stabilized Earth Retaining WallsAug. 1, 20238044125XPerformance Graded Asphalt BinderJan. 1, 20238045026Preformed Plastic Pavement MarkingJune 2, 2024* 3426127Railroad Protective Liability InsuranceDec. 1, 19868045528XRemoval and Disposal of Regulated SubstancesJan. 1, 20228045730Short Term and Temporary Pavement MarkingsApril 1, 20248045231Sign Panels and AppurtenancesJan. 1, 20258044832Source of Supply and Quality RequirementsJan. 1, 20228034733Speed Display TrailerApril 2, 20148039136Subcontractor and DBE Payment ReportingApril 2, 20148039138Subcontractor Mobilization PaymentsApril 2, 20148039138Surface Testing of Pavements – IRIJan. 1, 20218043737Submission of Payroll RecordsApril 1, 20218044738Unitra-Thin Bonded Wearing CourseApril 1, 20		80261	15		Construction Air Quality – Diesel Retrofit	June 1, 2010	Jan. 1, 2025
8045218Full Lane Sealant Waterproofing SystemNov. 1, 20238044719Grading and Shaping DitchesJan. 1, 20238043320Green Preformed Thermoplastic Pavement MarkingsJan. 1, 20248045621XHot-Mix AsphaltJan. 1, 20248045621XHot-Mix AsphaltJan. 1, 20228044622Hot-Mix AsphaltJoint SealantNov. 1, 20228043823Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 20218044725XPerformace Graded Asphalt BinderJan. 1, 20238044125XPerformace Graded Asphalt BinderJan. 1, 20238045926Preformed Plastic Pavement MarkingJune 2, 20248045528XRemoval and Disposal of Regulated SubstancesJan. 1, 20228045529SeedingNov. 1, 20228045529SeedingNov. 1, 20228045631Sign Panels and AppurtenancesJan. 1, 20248046231Sign Panels and AppurtenancesJan. 1, 20248046333Speed Display TrailerApril 2, 20148046432Source of Supply and Quality RequirementsJan. 2, 20238034135Subcontractor Mobilization Payment ReportingApril 2, 20148039136Subcontractor Mobilization PaymentsNov. 2, 20178039136Subcontractor Mobilization PaymentsNov. 2, 20178043737Submission of Payroll RecordsA	*	80029	16		Disadvantaged Business Enterprise Participation	Sept. 1, 2000	Mar. 2, 2019
8045218Full Lane Sealant Waterproofing SystemNov. 1, 20238044719Grading and Shaping DitchesJan. 1, 20238043320Green Preformed Thermoplastic Pavement MarkingsJan. 1, 20248045621XHot-Mix AsphaltJan. 1, 20248044622Hot-Mix AsphaltJan. 1, 2022Aug. 1, 20238044823Illinois Works Apprenticeship Initiative – State Funded ContractsNov. 1, 2022Aug. 1, 20238044125XPerformance Graded Asphalt BinderJan. 1, 2024April 2, 20248045526Preformed Plastic Pavement MarkingJune 2, 20248045528XRemoval and Disposal of Regulated SubstancesJan. 1, 20228045529SeedingNov. 1, 20228045529SeedingNov. 1, 20228045631Sign Panels and AppurtenancesJan. 1, 20248045530Short Term and Temporary Pavement MarkingsApril 1, 20248045631Sign Panels and AppurtenancesJan. 1, 20228044532Source of Supply and Quality RequirementsJan. 2, 20238030133Speed Display TrailerApril 2, 20148039136Subcontractor Mobilization Payment ReportingApril 2, 20148039136Subcontractor Mobilization PaymentsNov. 2, 20178043737Subcontractor Mobilization Payments – IRIJan. 1, 20218043738Surface Testing of Pavements – IRIJan. 1, 202180437		80229	17		Fuel Cost Adjustment	April 1, 2009	Aug. 1, 2017
8044719Grading and Shaping DitchesJan. 1, 20238043320Green Preformed Thermoplastic Pavement MarkingsJan. 1, 20218045621Hot-Mix AsphaltJan. 1, 20228045622Hot-Mix Asphalt - Longitudinal Joint SealantNov. 1, 20228043823Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 20218044624Mechanically Stabilized Earth Retaining WallsAug. 1, 20238044725Performance Graded Asphalt BinderJan. 1, 20238044526Preformed Plastic Pavement MarkingJune 2, 2024* 3426127Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528Removal and Disposal of Regulated SubstancesJan. 1, 2024April 1, 20248045730Short Term and Temporary Pavement MarkingsApril 1, 2024April 2, 20248045731Sign Panels and AppurtenancesJan. 1, 2025April 2, 20248044832Source of Supply and Quality RequirementsJan. 2, 2023Jan. 1, 20228034033Speed Display TrailerApril 2, 2014Jan. 1, 20228034736Subcontractor and DBE Payment ReportingApril 2, 2014Jan. 1, 20228034738Sufface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 20218034738Surface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 20228034739Training Special ProvisionsOct. 15, 1975Sept. 2, 2021 <t< td=""><td></td><td>80452</td><td>18</td><td></td><td>Full Lane Sealant Waterproofing System</td><td>Nov. 1, 2023</td><td>-</td></t<>		80452	18		Full Lane Sealant Waterproofing System	Nov. 1, 2023	-
8043320Green Preformed Thermoplastic Pavement MarkingsJan. 1, 2021Jan. 1, 20228045621XHot-Mix AsphaltJan. 1, 2024Jan. 1, 20258044622Hot-Mix Asphalt - Longitudinal Joint SealantNov. 1, 2022Aug. 1, 20238043823Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 2021April 2, 20248045024Mechanically Stabilized Earth Retaining WallsAug. 1, 2023April 2, 20248044125XPerformance Graded Asphalt BinderJan. 1, 20238045926Preformed Plastic Pavement MarkingJune 2, 2024*3426I27Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528XRemoval and Disposal of Regulated SubstancesJan. 1, 2024April 1, 20248045730Short Term and Temporary Pavement MarkingsApril 1, 2024April 2, 20248045831Sign Panels and AppurtenancesJan. 1, 2025April 2, 20248044832Source of Supply and Quality RequirementsJan. 1, 2025Jan. 1, 20228047730Steel Cost AdjustmentApril 2, 2014Jan. 1, 20228047831Sign Panels and AppurtenancesJan. 1, 2025Jan. 1, 20228048832Source of Supply and Quality RequirementsJan. 1, 2021Jan. 1, 20228047734Steel Cost AdjustmentApril 2, 2014Jan. 1, 20228039136Subcontractor Mobilization PaymentsNov.		80447	19	\Box			
8045621XHot-Mix AsphaltJan. 1, 2024Jan. 1, 2024Jan. 1, 20258044622Hot-Mix Asphalt - Longitudinal Joint SealantNov. 1, 2022Aug. 1, 20238043823Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 2021April 2, 20248045024Mechanically Stabilized Earth Retaining WallsAug. 1, 2023April 2, 20248045926Performance Graded Asphalt BinderJan. 1, 2023June 2, 2024*3426127Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528Removal and Disposal of Regulated SubstancesJan. 1, 2024April 1, 20248045730Short Term and Temporary Pavement MarkingsApril 1, 2024April 2, 20248045831Sign Panels and AppurtenancesJan. 1, 2025April 2, 20248045730Short Term and Temporary Pavement MarkingsApril 2, 2014Jan. 1, 20228045730Short Term and Temporary Pavement MarkingsApril 2, 2014April 2, 20248046231Sign Panels and AppurtenancesJan. 1, 2025Jan. 1, 20228045735Subcontractor and DBE Payment ReportingApril 2, 2014Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 2014Jan. 1, 20218039136Subcontractor Mobilization PaymentsMov. 2, 2017April 1, 20198043538Surface Testing of Payroll RecordsApril 1, 2021Nov. 2, 2023		80433	20	\Box			Jan. 1, 2022
8044622Hot-Mix Asphalt - Longitudinal Joint SealantNov. 1, 2022Aug. 1, 20238043823Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 2021April 2, 20248045024Mechanically Stabilized Earth Retaining WallsAug. 1, 2023April 2, 20248045125Performace Graded Asphalt BinderJan. 1, 2023June 2, 2024*3426127Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528XRemoval and Disposal of Regulated SubstancesJan. 1, 2024April 1, 20248045730Short Term and Temporary Pavement MarkingsApril 1, 2024April 2, 20248045832Source of Supply and Quality RequirementsJan. 1, 2025April 2, 20248044832Source of Supply and Quality RequirementsJan. 1, 2022Jan. 1, 20228034033Speed Display TrailerApril 2, 2014Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 2014Jan. 1, 20228039736Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198039136Subcontractor Mobilization PaymentsApril 1, 2021Nov. 2, 2023*203839Training Special ProvisionsOct. 15, 1975Sept. 2, 2024*4042Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228045941Weekly DBE Trucking ReportsAug. 1, 2024Nov. 1, 2022*Waterproofi				X			
8043823Illinois Works Apprenticeship Initiative – State Funded ContractsJune 2, 2021April 2, 20248045024Mechanically Stabilized Earth Retaining WallsAug. 1, 2023Jan. 1, 20238044125XPerformance Graded Asphalt BinderJan. 1, 2023June 2, 2024*3426127Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528XRemoval and Disposal of Regulated SubstancesJan. 1, 2024April 1, 20248045730Short Term and Temporary Pavement MarkingsApril 1, 2024April 2, 20248046831Sign Panels and AppurtenancesJan. 2, 20238044832Source of Supply and Quality RequirementsJan. 2, 20238034033Speed Display TrailerApril 2, 2014Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 2014Jan. 1, 20228039736Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20148039136Subractor Mobilizer Payments – IRIJan. 1, 2021Nov. 2, 2023*2033839Training Special ProvisionsOct. 15, 1975Sept. 2, 2024*2043840Ultra-Thin Bonded Wearing CourseApril 1, 2021Nov. 1, 20228043941XVehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228043943Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021							
8045024Mechanically Stabilized Earth Retaining WallsAug. 1, 20238044125XPerformance Graded Asphalt BinderJan. 1, 20238045926Preformed Plastic Pavement MarkingJune 2, 2024*3426127Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528XRemoval and Disposal of Regulated SubstancesJan. 1, 2024April 1, 20248045730Short Term and Temporary Pavement MarkingsApril 1, 2024April 2, 20248045231Sign Panels and AppurtenancesJan. 1, 2025Source of Supply and Quality RequirementsJan. 1, 20258044832Source of Supply and Quality RequirementsJan. 2, 2023Jan. 1, 20228034033Speed Display TrailerApril 2, 2014Jan. 1, 20228037735Subcontractor AdjustmentApril 2, 2014Jan. 1, 20228039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043538Surface Testing of Pavements – IRIJan. 1, 2021Nov. 2, 20238043539Training Special ProvisionsOct. 15, 1975Sept. 2, 2024*203839Training Special ProvisionsOct. 15, 1975Sept. 2, 20248043941X Vehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228043542Waterproofing Membrane SystemAug. 1, 2024Nov. 1, 20248030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 20				П			
8044125XPerformance Graded Asphalt BinderJan. 1, 20238045926Preformed Plastic Pavement MarkingJune 2, 2024*3426I27Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528XRemoval and Disposal of Regulated SubstancesJan. 1, 2024April 1, 20248045730Short Term and Temporary Pavement MarkingsNov. 1, 2022April 2, 20248045730Short Term and Temporary Pavement MarkingsJan. 1, 2024April 2, 20248046231Sign Panels and AppurtenancesJan. 2, 2023Source of Supply and Quality RequirementsJan. 2, 20238034033Speed Display TrailerApril 2, 2014Jan. 1, 2022Jan. 1, 2022803735Subcontractor and DBE Payment ReportingApril 2, 2014Jan. 1, 20228039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 2023*203839Training Special ProvisionsOct. 15, 1975Sept. 2, 2024*2043940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941XVehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228042943Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2024				Ы			, .p, _o
8045926Preformed Plastic Pavement MarkingJune 2, 2024*3426127Railroad Protective Liability InsuranceDec. 1, 1986Jan. 1, 20228045528XRemoval and Disposal of Regulated SubstancesJan. 1, 2024April 1, 20248044529SeedingNov. 1, 2022April 2, 20248045730Short Term and Temporary Pavement MarkingsApril 1, 2024April 2, 20248046231Sign Panels and AppurtenancesJan. 1, 2025April 2, 20248044832Source of Supply and Quality RequirementsJan. 2, 2023Source of Supply and Quality Requirements8044933Speed Display TrailerApril 2, 2014Jan. 1, 20228030735Subcontractor and DBE Payment ReportingApril 2, 2014Jan. 1, 20228039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 2023*203839Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 2022Jan. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024Nov. 1, 20228030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021						-	
 * 3426l 27 Railroad Protective Liability Insurance 80455 28 Removal and Disposal of Regulated Substances 9 Seeding 80445 29 Seeding 80457 30 Short Term and Temporary Pavement Markings 80457 30 Short Term and Temporary Pavement Markings 80457 30 Short Term and Temporary Pavement Markings 80462 31 Sign Panels and Appurtenances 80448 32 Source of Supply and Quality Requirements 80340 33 Speed Display Trailer 80340 33 Speed Display Trailer 80397 35 Subcontractor and DBE Payment Reporting 80391 36 Subcontractor Mobilization Payments 80437 37 Submission of Payroll Records 80438 38 Surface Testing of Pavements – IRI 80439 39 Training Special Provisions 80429 40 Ultra-Thin Bonded Wearing Course 80439 41 X Vehicle and Equipment Warning Lights 80302 43 Weekly DBE Trucking Reports 				Ë			
8045528XRemoval and Disposal of Regulated SubstancesJan. 1, 2024April 1, 20248044529SeedingNov. 1, 20228045730Short Term and Temporary Pavement MarkingsApril 1, 20248046231Sign Panels and AppurtenancesJan. 1, 20258044832Source of Supply and Quality RequirementsJan. 2, 20238034033Speed Display TrailerApril 2, 2014Jan. 1, 20228012734Steel Cost AdjustmentApril 2, 2004Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 2017April 1, 20198043737Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043538Surface Testing of Pavements – IRIJan. 1, 2021Nov. 2, 20238042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941Vehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024Nov. 1, 20218030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021	*			H			lan 1 2022
8044529SeedingNov. 1, 20228045730Short Term and Temporary Pavement MarkingsApril 1, 20248046231Sign Panels and AppurtenancesJan. 1, 20258044832Source of Supply and Quality RequirementsJan. 2, 20238034033Speed Display TrailerApril 2, 2014Jan. 1, 20228012734Steel Cost AdjustmentApril 2, 2004Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 20188039136Subcontractor Mobilization PaymentsNov. 2, 20178043737Submission of Payroll RecordsApril 1, 20218043538Surface Testing of Pavements – IRIJan. 1, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941Vehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024Nov. 1, 20218030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021							
8045730Short Term and Temporary Pavement MarkingsApril 1, 2024April 2, 20248046231Sign Panels and AppurtenancesJan. 1, 20258044832Source of Supply and Quality RequirementsJan. 2, 20238034033Speed Display TrailerApril 2, 2014Jan. 1, 20228012734Steel Cost AdjustmentApril 2, 2004Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 20188039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 20238043538Surface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 2023*2033839Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2021Nov. 1, 20228043941Vehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024Nov. 1, 20218030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021							April 1, 2024
8046231Sign Panels and AppurtenancesJan. 1, 20258044832Source of Supply and Quality RequirementsJan. 2, 20238034033Speed Display TrailerApril 2, 2014Jan. 1, 20228012734Steel Cost AdjustmentApril 2, 2004Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 2017April 1, 20198039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 20238043538Surface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 2023*2033839Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043842Waterproofing Membrane SystemAug. 1, 2024Nov. 1, 20218030243Weekly DBE Trucking ReportsAug. 1, 2024Nov. 1, 2021				H			April 2 2024
8044832Source of Supply and Quality RequirementsJan. 2, 20238034033Speed Display TrailerApril 2, 2014Jan. 1, 20228012734Steel Cost AdjustmentApril 2, 2004Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 20188039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 20238043538Surface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 2023*20338Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043841Vehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024June 2, 2012Nov. 1, 20218030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021				H			April 2, 2024
8034033Speed Display TrailerApril 2, 2014Jan. 1, 20228012734Steel Cost AdjustmentApril 2, 2004Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 20188039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 20238043538Surface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 2023*2033839Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941XVehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024June 2, 2012Nov. 1, 20218030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021				Н			
8012734Steel Cost AdjustmentApril 2, 2004Jan. 1, 20228039735Subcontractor and DBE Payment ReportingApril 2, 20188039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 20238043538Surface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 2023*2033839Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941XVehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024June 2, 2012Nov. 1, 20218030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021				H			lan 1 2022
8039735Subcontractor and DBE Payment ReportingApril 2, 20188039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 20238043538Surface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 2023*20338Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941XVehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024June 2, 2012Nov. 1, 20218030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021				H			
8039136Subcontractor Mobilization PaymentsNov. 2, 2017April 1, 20198043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 20238043538Surface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 2023*20338Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941Vehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024June 2, 2012Nov. 1, 20218030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021Nov. 1, 2021				H			Jan. 1, 2022
8043737Submission of Payroll RecordsApril 1, 2021Nov. 2, 20238043538Surface Testing of Pavements – IRIJan. 1, 2021Jan. 1, 2023*20338Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941Vehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024June 2, 20128030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021				H			
80435 38 Surface Testing of Pavements – IRI Jan. 1, 2021 Jan. 1, 2023 * 20338 Training Special Provisions Oct. 15, 1975 Sept. 2, 2021 80429 40 Ultra-Thin Bonded Wearing Course April 1, 2020 Jan. 1, 2022 80439 41 Vehicle and Equipment Warning Lights Nov. 1, 2021 Nov. 1, 2022 80458 42 Waterproofing Membrane System Aug. 1, 2024 June 2, 2012 Nov. 1, 2021				H			
*2033839Training Special ProvisionsOct. 15, 1975Sept. 2, 20218042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941XVehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 2024June 2, 2012Nov. 1, 20218030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021							
8042940Ultra-Thin Bonded Wearing CourseApril 1, 2020Jan. 1, 20228043941XVehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 20248030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021				Ц			
8043941XVehicle and Equipment Warning LightsNov. 1, 2021Nov. 1, 20228045842Waterproofing Membrane SystemAug. 1, 20248030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021	*			Ц			
8045842Waterproofing Membrane SystemAug. 1, 20248030243Weekly DBE Trucking ReportsJune 2, 2012Nov. 1, 2021				Ц			
80302 43 🔲 Weekly DBE Trucking Reports June 2, 2012 Nov. 1, 2021				M			Nov. 1, 2022
				Ц			
004E4 44 Mood Cign Cupport				Ц			Nov. 1, 2021
		80454			Wood Sign Support	Nov. 1, 2023	
80427 45 🔲 Work Zone Traffic Control Devices Mar. 2, 2020 Jan. 1, 2025							Jan. 1, 2025
* 80071 46 🔲 Working Days Jan. 1, 2002	*	80071	46		Working Days	Jan. 1, 2002	

Highlighted items indicate a new or revised special provision for the letting.

An * indicates the special provision requires additional information from the designer, which needs to be submitted separately. The Project Coordination and Implementation Section will then include the information in the applicable special provision.

The following special provisions have been deleted from use.

<u>File Name</u>	Special Provision Title	Effective	Revised
80449	Cement, Type IL	Aug. 1, 2023	
80451	Portland Cement Concrete	Aug. 1, 2023	

The following special provisions are in the 2025 Supplemental Specifications and Recurring Special Provisions.

<u>File Name</u>	Special Provision Title	New Location(s)	Effective	Revised
80434	Corrugated Plastic Pipe (Culvert and Storm	Articles 542.03, 550.03, 1040.03,	Jan. 1, 2021	
	Sewer)	1040.04(b), 1040.04(d) & 1040.08		
80443	High Tension Cable Median Barrier Removal	Section 632	April 1, 2022	
80045	Material Transfer Device	Articles 406.03, 406.06(f), 406.13(b),	Nov 15, 1999	Jan. 1, 2022
		406.14 & 1102.02		
80410	Traffic Spotters	Article 701.13	Jan. 1, 2019	

COMPENSABLE DELAY COSTS (BDE)

Effective: June 2, 2017 Revised: April 1, 2019

Revise Article 107.40(b) of the Standard Specifications to read:

- "(b) Compensation. Compensation will not be allowed for delays, inconveniences, or damages sustained by the Contractor from conflicts with facilities not meeting the above definition; or if a conflict with a utility in an unanticipated location does not cause a shutdown of the work or a documentable reduction in the rate of progress exceeding the limits set herein. The provisions of Article 104.03 notwithstanding, compensation for delays caused by a utility in an unanticipated location will be paid according to the provisions of this Article governing minor and major delays or reduced rate of production which are defined as follows.
 - (1) Minor Delay. A minor delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two hours, but not to exceed two weeks.
 - (2) Major Delay. A major delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two weeks.
 - (3) Reduced Rate of Production Delay. A reduced rate of production delay occurs when the rate of production on the work in conflict with the utility in an unanticipated location decreases by more than 25 percent and lasts longer than seven calendar days."

Revise Article 107.40(c) of the Standard Specifications to read:

- "(c) Payment. Payment for Minor, Major, and Reduced Rate of Production Delays will be made as follows.
 - (1) Minor Delay. Labor idled which cannot be used on other work will be paid for according to Article 109.04(b)(1) and (2) for the time between start of the delay and the minimum remaining hours in the work shift required by the prevailing practice in the area.

Equipment idled which cannot be used on other work, and which is authorized to standby on the project site by the Engineer, will be paid for according to Article 109.04(b)(4).

(2) Major Delay. Labor will be the same as for a minor delay.

Equipment will be the same as for a minor delay, except Contractor-owned equipment will be limited to two weeks plus the cost of move-out to either the

Contractor's yard or another job and the cost to re-mobilize, whichever is less. Rental equipment may be paid for longer than two weeks provided the Contractor presents adequate support to the Department (including lease agreement) to show retaining equipment on the job is the most economical course to follow and in the public interest.

(3) Reduced Rate of Production Delay. The Contractor will be compensated for the reduced productivity for labor and equipment time in excess of the 25 percent threshold for that portion of the delay in excess of seven calendar days. Determination of compensation will be in accordance with Article 104.02, except labor and material additives will not be permitted.

Payment for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be determined according to Article 109.13."

Revise Article 108.04(b) of the Standard Specifications to read:

- "(b) No working day will be charged under the following conditions.
 - (1) When adverse weather prevents work on the controlling item.
 - (2) When job conditions due to recent weather prevent work on the controlling item.
 - (3) When conduct or lack of conduct by the Department or its consultants, representatives, officers, agents, or employees; delay by the Department in making the site available; or delay in furnishing any items required to be furnished to the Contractor by the Department prevents work on the controlling item.
 - (4) When delays caused by utility or railroad adjustments prevent work on the controlling item.
 - (5) When strikes, lock-outs, extraordinary delays in transportation, or inability to procure critical materials prevent work on the controlling item, as long as these delays are not due to any fault of the Contractor.
 - (6) When any condition over which the Contractor has no control prevents work on the controlling item."

Revise Article 109.09(f) of the Standard Specifications to read:

"(f) Basis of Payment. After resolution of a claim in favor of the Contractor, any adjustment in time required for the work will be made according to Section 108. Any adjustment in the costs to be paid will be made for direct labor, direct materials, direct equipment, direct jobsite overhead, direct offsite overhead, and other direct costs allowed by the resolution. Adjustments in costs will not be made for interest charges, loss of anticipated profit, undocumented loss of efficiency, home office overhead and unabsorbed overhead other than as allowed by Article 109.13, lost opportunity, preparation of claim expenses and other consequential indirect costs regardless of method of calculation.

The above Basis of Payment is an essential element of the contract and the claim cost recovery of the Contractor shall be so limited."

Add the following to Section 109 of the Standard Specifications.

"**109.13 Payment for Contract Delay.** Compensation for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be allowed when such costs result from a delay meeting the criteria in the following table.

Contract Type	Cause of Delay	Length of Delay
Working Days	Article 108.04(b)(3) or Article 108.04(b)(4)	No working days have been charged for two consecutive weeks.
Completion Article 108.08(b)(1) or		The Contractor has been granted a minimum two week extension of contract time, according to Article 108.08.

Payment for each of the various costs will be according to the following.

- (a) Escalated Material and/or Labor Costs. When the delay causes work, which would have otherwise been completed, to be done after material and/or labor costs have increased, such increases will be paid. Payment for escalated material costs will be limited to the increased costs substantiated by documentation furnished by the Contractor. Payment for escalated labor costs will be limited to those items in Article 109.04(b)(1) and (2), except the 35 percent and 10 percent additives will not be permitted.
- (b) Extended Project Overhead. For the duration of the delay, payment for extended project overhead will be paid as follows.
 - (1) Direct Jobsite and Offsite Overhead. Payment for documented direct jobsite overhead and documented direct offsite overhead, including onsite supervisory and administrative personnel, will be allowed according to the following table.

Original Contract Amount	Supervisory and Administrative Personnel
Up to \$5,000,000	One Project Superintendent
Over \$ 5,000,000 - up to \$25,000,000	One Project Manager, One Project Superintendent or Engineer, and One Clerk
Over \$25,000,000 - up to \$50,000,000	One Project Manager, One Project Superintendent, One Engineer, and

	One Clerk
Over \$50,000,000	One Project Manager, Two Project Superintendents,
	One Engineer, and One Clerk

- (2) Home Office and Unabsorbed Overhead. Payment for home office and unabsorbed overhead will be calculated as 8 percent of the total delay cost.
- (c) Extended Traffic Control. Traffic control required for an extended period of time due to the delay will be paid for according to Article 109.04.

When an extended traffic control adjustment is paid under this provision, an adjusted unit price as provided for in Article 701.20(a) for increase or decrease in the value of work by more than ten percent will not be paid.

Upon payment for a contract delay under this provision, the Contractor shall assign subrogation rights to the Department for the Department's efforts of recovery from any other party for monies paid by the Department as a result of any claim under this provision. The Contractor shall fully cooperate with the Department in its efforts to recover from another party any money paid to the Contractor for delay damages under this provision."

80384

HOT-MIX ASPHALT (BDE)

Effective: January 1, 2024 Revised: January 1, 2025

Revise the first and second paragraphs of Articles 1030.06(c)(2) of the Standard Specifications to read:

"(2) Personnel. The Contractor shall provide a QC Manager who shall have overall responsibility and authority for quality control. This individual shall maintain active certification as a Hot-Mix Asphalt Level II technician.

In addition to the QC Manager, the Contractor shall provide sufficient personnel to perform the required visual inspections, sampling, testing, and documentation in a timely manner. Mix designs shall be developed by personnel with an active certification as a Hot-Mix Asphalt Level III technician. Technicians performing mix design testing and plant sampling/testing shall maintain active certification as a Hot-Mix Asphalt Level III technician active certification as a Hot-Mix Asphalt Level I technician. The Contractor may provide a technician trainee who has successfully completed the Department's "Hot-Mix Asphalt Level I technician for a period of one year after the course completion date. The Contractor may also provide a Gradation Technician who has successfully completed the Department's "Gradation Technician Course" to run gradation tests only under the supervision of a Hot-Mix Asphalt Level II Technician. The Contractor shall provide a Hot-Mix Asphalt Density Tester who has successfully completed the Department's "Nuclear Density Testing" course to run all nuclear density tests on the job site."

Revise the second paragraph of Articles 1030.07(a)(11) and 1030.08(a)(9) of the Standard Specifications to read:

"When establishing the target density, the HMA maximum theoretical specific gravity (G_{mm}) will be based on the running average of four available Department test results for that project. If less than four G_{mm} test results are available, an average of all available Department test results for that project will be used. The initial G_{mm} will be the last available Department test result from a QMP project. If there is no available Department test result from a QMP project. If there is no available Department test result from a QMP project, the Department mix design verification test result will be used as the initial G_{mm} ."

Revise Article 1030.09(g)(2) of the Standard Specifications to read:

"(2) The Contractor shall complete split verification sample tests listed in the Limits of Precision table in Article 1030.09(h)(1)."

In the Supplemental Specifications, replace the revision for the end of the third paragraph of Article 1030.09(h)(2) with the following:

"When establishing the target density, the HMA maximum theoretical specific gravity (G_{mm}) will be the Department mix design verification test result."

Revise the tenth paragraph of Article 1030.10 of the Standard Specifications to read:

"Production is not required to stop after a test strip has been constructed."

80456

PERFORMANCE GRADED ASPHALT BINDER (BDE)

Effective: January 1, 2023

Revise Article 1032.05 of the Standard Specifications to read:

"1032.05 Performance Graded Asphalt Binder. These materials will be accepted according to the Bureau of Materials Policy Memorandum, "Performance Graded Asphalt Binder Qualification Procedure." The Department will maintain a qualified producer list. These materials shall be free from water and shall not foam when heated to any temperature below the actual flash point. Air blown asphalt, recycle engine oil bottoms (ReOB), and polyphosphoric acid (PPA) modification shall not be used.

When requested, producers shall provide the Engineer with viscosity/temperature relationships for the performance graded asphalt binders delivered and incorporated in the work.

(a) Performance Graded (PG) Asphalt Binder. The asphalt binder shall meet the requirements of AASHTO M 320, Table 1 "Standard Specification for Performance Graded Asphalt Binder" for the grade shown on the plans and the following.

Test	Parameter
Small Strain Parameter (AASHTO PP 113) BBR, ΔTc, 40 hrs PAV (40 hrs continuous or 2 PAV at 20 hrs)	-5 °C min.

(b) Modified Performance Graded (PG) Asphalt Binder. The asphalt binder shall meet the requirements of AASHTO M 320, Table 1 "Standard Specification for Performance Graded Asphalt Binder" for the grade shown on the plans.

Asphalt binder modification shall be performed at the source, as defined in the Bureau of Materials Policy Memorandum, "Performance Graded Asphalt Binder Qualification Procedure."

Modified asphalt binder shall be safe to handle at asphalt binder production and storage temperatures or HMA construction temperatures. Safety Data Sheets (SDS) shall be provided for all asphalt modifiers.

(1) Polymer Modification (SB/SBS or SBR). Elastomers shall be added to the base asphalt binder to achieve the specified performance grade and shall be either a styrene-butadiene diblock, triblock copolymer without oil extension, or a styrenebutadiene rubber. The polymer modified asphalt binder shall be smooth, homogeneous, and be according to the requirements shown in Table 1 or 2 for the grade shown on the plans.

[
Table 1 - Requirements for Styrene-Butadiene Copolymer (SB/SBS) Modified Asphalt Binders			
Test	Asphalt Grade SB/SBS PG 64-28 SB/SBS PG 70-22	Asphalt Grade SB/SBS PG 64-34 SB/SBS PG 70-28 SB/SBS PG 76-22 SB/SBS PG 76-28	
Separation of Polymer ITP, "Separation of Polymer from Asphalt Binder" Difference in °F (°C) of the softening point between top and bottom portions	4 (2) max.	4 (2) max.	
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	60 min.	70 min.	

Table 2 - Requirements for Styrene-Butadiene Rubber (SBR) Modified Asphalt Binders			
Test	Asphalt Grade SBR PG 64-28 SBR PG 70-22	Asphalt Grade SB/SBS PG 64-34 SB/SBS PG 70-28 SBR PG 76-22 SBR PG 76-28	
Separation of Polymer ITP, "Separation of Polymer from Asphalt Binder" Difference in °F (°C) of the softening			
point between top and bottom portions Toughness ASTM D 5801, 77 °F (25 °C), 20 in./min. (500 mm/min.), inlbs (N-m)	4 (2) max. 110 (12.5) min.	4 (2) max. 110 (12.5) min.	
Tenacity ASTM D 5801, 77 °F (25 °C), 20 in./min. (500 mm/min.), inlbs (N-m)	75 (8.5) min.	75 (8.5) min.	
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %	40 min.	50 min.	

(2) Ground Tire Rubber (GTR) Modification. GTR modification is the addition of recycled ground tire rubber to liquid asphalt binder to achieve the specified performance grade. GTR shall be produced from processing automobile and/or truck tires by the ambient

grinding method or micronizing through a cryogenic process. GTR shall not exceed 1/16 in. (2 mm) in any dimension and shall not contain free metal particles, moisture that would cause foaming of the asphalt, or other foreign materials. A mineral powder (such as talc) meeting the requirements of AASHTO M 17 may be added, up to a maximum of four percent by weight of GTR to reduce sticking and caking of the GTR particles. When tested in accordance with Illinois Modified AASHTO T 27 "Standard Method of Test for Sieve Analysis of Fine and Coarse Aggregates" or AASHTO PP 74 "Standard Practice for Determination of Size and Shape of Glass Beads Used in Traffic Markings by Means of Computerized Optical Method", a 50 g sample of the GTR shall conform to the following gradation requirements.

Sieve Size	Percent Passing
No. 16 (1.18 mm)	100
No. 30 (600 μm)	95 ± 5
No. 50 (300 µm)	> 20

GTR modified asphalt binder shall be tested for rotational viscosity according to AASHTO T 316 using spindle S27. GTR modified asphalt binder shall be tested for original dynamic shear and RTFO dynamic shear according to AASHTO T 315 using a gap of 2 mm.

The GTR modified asphalt binder shall meet the requirements of Table 3.

Table 3 - Requirements for Ground Tire Rubber (GTR) Modified Asphalt Binders			
Test Asphalt Grade GTR PG 64-28 GTR PG 70-22 GTR PG 70-22 GTR PG 70-28			
TESTS ON RESIDUE FROM ROLLING THIN FILM OVEN TEST (AASHTO T 240)			
Elastic Recovery ASTM D 6084, Procedure A, 77 °F (25 °C), 100 mm elongation, %60 min.70 min.			

(3) Softener Modification (SM). Softener modification is the addition of organic compounds, such as engineered flux, bio-oil blends, modified vegetable oils, glycol amines, and fatty acid derivatives, to the base asphalt binder to achieve the specified performance grade. Softeners shall be dissolved, dispersed, or reacted in the asphalt binder to enhance its performance and shall remain compatible with the asphalt binder with no separation. Softeners shall not be added to modified PG asphalt binder as defined in Articles 1032.05(b)(1) or 1032.05(b)(2).

An Attenuated Total Reflectance-Fourier Transform Infrared spectrum (ATR-FTIR) shall be collected for both the softening compound as well as the softener modified

asphalt binder at the dose intended for qualification. The ATR-FTIR spectra shall be collected on unaged softener modified binder, 20-hour Pressurized Aging Vessel (PAV) aged softener modified binder, and 40-hour PAV aged softener modified binder. The ATR-FTIR shall be collected in accordance with Illinois Test Procedure 601. The electronic files spectral files (in one of the following extensions or equivalent: *.SPA, *.SPG, *.IRD, *.IFG, *.CSV, *.SP, *.IRS, *.GAML, *.[0-9], *.IGM, *.ABS, *.DRT, *.SBM, *.RAS) shall be submitted to the Central Bureau of Materials.

Softener modified asphalt binders shall meet the requirements in Table 4.

Table 4 - Requirements for Softener Modified Asphalt Binders		
	Asphalt Grade	
	SM PG 46-28 SM PG 46-34	
Test	SM PG 52-28 SM PG 52-34	
	SM PG 58-22 SM PG 58-28	
	SM PG 64-22	
Small Strain Parameter (AASHTO PP 113)		
BBR, ΔTc, 40 hrs PAV (40 hrs	-5°C min.	
continuous or 2 PAV at 20 hrs)		
Large Strain Parameter (Illinois Modified		
AASHTO T 391) DSR/LAS Fatigue	≥ 54 %	
Property, Δ G* peak τ, 40 hrs PAV		
(40 hrs continuous or 2 PAV at 20 hrs)		

The following grades may be specified as tack coats.

Asphalt Grade	Use
PG 58-22, PG 58-28, PG 64-22	Tack Coat"

Revise Article 1031.06(c)(1) and 1031.06(c)(2) of the Standard Specifications to read:

"(1) RAP/RAS. When RAP is used alone or RAP is used in conjunction with RAS, the percentage of virgin ABR shall not exceed the amounts listed in the following table.

HMA Mixtures - RAP/RAS Maximum ABR % ^{1/2/}			
Ndesign Binder Surface Polymer Modified Binder or Surface 3			
30	30	30	10
50	25	15	10
70	15	10	10
90	10	10	10

1/ For Low ESAL HMA shoulder and stabilized subbase, the RAP/RAS ABR shall not exceed 50 percent of the mixture.

- 2/ When RAP/RAS ABR exceeds 20 percent, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- 3/ The maximum ABR percentages for ground tire rubber (GTR) modified mixes shall be equivalent to the percentages specified for SBS/SBR polymer modified mixes.
- (2) FRAP/RAS. When FRAP is used alone or FRAP is used in conjunction with RAS, the percentage of virgin asphalt binder replacement shall not exceed the amounts listed in the following table.

HMA Mixtures - FRAP/RAS Maximum ABR % ^{1/2/}			
Ndesign	Binder	Surface	Polymer Modified Binder or Surface ^{3/}
30	55	45	15
50	45	40	15
70	45	35	15
90	45	35	15
SMA			25
IL-4.75			35

- 1/ For Low ESAL HMA shoulder and stabilized subbase, the FRAP/RAS ABR shall not exceed 50 percent of the mixture.
- 2/ When FRAP/RAS ABR exceeds 20 percent for all mixes, the high and low virgin asphalt binder grades shall each be reduced by one grade (i.e. 25 percent ABR would require a virgin asphalt binder grade of PG 64-22 to be reduced to a PG 58-28).
- 3/ The maximum ABR percentages for GTR modified mixes shall be equivalent to the percentages specified for SBS/SBR polymer modified mixes."

Add the following to the end of Note 2 of Article 1030.03 of the Standard Specifications.

"A dedicated storage tank for the ground tire rubber (GTR) modified asphalt binder shall be provided. This tank shall be capable of providing continuous mechanical mixing throughout and/or recirculation of the asphalt binder to provide a uniform mixture. The tank shall be heated and capable of maintaining the temperature of the asphalt binder at 300 °F to 350 °F (149 °C to 177 °C). The asphalt binder metering systems of dryer drum plants shall be calibrated with the actual GTR modified asphalt binder material with an accuracy of ± 0.40 percent."

80441

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)

Effective: January 1, 2024 Revised: April 1, 2024

Revise the first paragraph of Article 669.04 of the Standard Specifications to read:

"669.04 Regulated Substances Monitoring. Regulated substances monitoring includes environmental observation and field screening during regulated substances management activities. The excavated soil and groundwater within the work areas shall be managed as either uncontaminated soil, hazardous waste, special waste, or non-special waste.

As part of the regulated substances monitoring, the monitoring personnel shall perform and document the applicable duties listed on form BDE 2732 "Regulated Substances Monitoring Daily Record (RSMDR)"."

Revise the first two sentences of the nineteenth paragraph of Article 669.05 of the Standard Specifications to read:

"The Contractor shall coordinate waste disposal approvals with the disposal facility and provide the specific analytical testing requirements of that facility. The Contractor shall make all arrangements for collection, transportation, and analysis of landfill acceptance testing."

Revise the last paragraph of Article 669.05 of the Standard Specifications to read:

"The Contractor shall select a permitted landfill facility or CCDD/USFO facility meeting the requirements of 35 III. Admin. Code Parts 810-814 or Part 1100, respectively. The Department will review and approve or reject the facility proposed by the Contractor based upon information provided in BDE 2730. The Contractor shall verify whether the selected facility is compliant with those applicable standards as mandated by their permit and whether the facility is presently, has previously been, or has never been, on the United States Environmental Protection Agency (U.S. EPA) National Priorities List or the Resource Conservation and Recovery Act (RCRA) List of Violating Facilities. The use of a Contractor selected facility shall in no manner delay the construction schedule or alter the Contractor's responsibilities as set forth."

Revise the first paragraph of Article 669.07 of the Standard Specifications to read:

"669.07 Temporary Staging. Soil classified according to Articles 669.05(a)(2), (b)(1), or (c) may be temporarily staged at the Contractor's option. All other soil classified according to Articles 669.05(a)(1), (a)(3), (a)(4), (a)(5), (a)(6), or (b)(2) shall be managed and disposed of without temporary staging to the greatest extent practicable. If circumstances beyond the Contractor's control require temporary staging of these latter materials, the Contractor shall request approval from the Engineer in writing.

Topsoil for re-use as final cover which has been field screened and found not to exhibit PID readings over daily background readings as documented on the BDE 2732, visual staining or

odors, and is classified according to Articles 669.05(a)(2), (a)(3), (a)(4), (b)(1), or (c) may be temporarily staged at the Contractor's option."

Add the following paragraph after the sixth paragraph of Article 669.11 of the Standard Specifications.

"The sampling and testing of effluent water derived from dewatering discharges for priority pollutants volatile organic compounds (VOCs), priority pollutants semi-volatile organic compounds (SVOCs), or priority pollutants metals, will be paid for at the contract unit price per each for VOCS GROUNDWATER ANALYSIS using EPA Method 8260B, SVOCS GROUNDWATER ANALYSIS using EPA Method 8270C, or RCRA METALS GROUNDWATER ANALYSIS using EPA Methods 6010B and 7471A. This price shall include transporting the sample from the job site to the laboratory."

Revise the first sentence of the eight paragraph of Article 669.11 of the Standard Specifications to read:

"Payment for temporary staging of soil classified according to Articles 669.05(a)(1), (a)(3), (a)(4), (a)(5), (a)(6), or (b)(2) to be managed and disposed of, if required and approved by the Engineer, will be paid according to Article 109.04."

80455

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)

Effective: November 1, 2021 Revised: November 1, 2022

Add the following paragraph after the first paragraph of Article 701.08 of the Standard Specifications:

"The Contractor shall equip all vehicles and equipment with high-intensity oscillating, rotating, or flashing, amber or amber-and-white, warning lights which are visible from all directions. In accordance with 625 ILCS 5/12-215, the lights may only be in operation while the vehicle or equipment is engaged in construction operations."

80439

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR INSURANCE

Effective: February 1, 2007 Revised: August 1, 2007

All references to Sections or Articles in this specification shall be construed to mean specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

The Contractor shall name the following entities as additional insured under the Contractor's general liability insurance policy in accordance with Article 107.27:

Washington Road District

Tazewell County

The entities listed above and their officers, employees, and agents shall be indemnified and held harmless in accordance with Article 107.26.

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR EQUIPMENT RENTAL RATES

Effective: January 1, 2012

All references to Sections or Articles in this specification shall be construed to mean a specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

Replace Article 109.04(b)(4) with the following:

"(4) Equipment. For any machinery or special equipment (other than small tools) the use of which has been authorized by the Engineer, the Contractor will be paid according to the latest revision of "SCHEDULE OF AVERAGE ANNUAL EQUIPMENT OWNERSHIP EXPENSE" and latest index factor as issued by the Illinois Department of Transportation. The equipment should be of a type and size reasonably required to complete the extra work."

State of Illinois Department of Transportation Bureau of Local Roads and Streets

SPECIAL PROVISION FOR CONSTRUCTION AND MAINTENANCE SIGNS

Effective: January 1, 2004 Revised: June 1, 2007

All references to Sections or Articles in this specification shall be construed to mean a specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

701.14. <u>Signs</u>. Add the following paragraph to Article 701.14:

All warning signs shall have minimum dimensions of 1200 mm x 1200 mm (48" x 48") and have a black legend on a fluorescent orange reflectorized background, meeting, as a minimum, Type AP reflectivity requirements of Table 1091-2 in Article 1091.02.

State of Illinois DEPARTMENT OF TRANSPORTATION Bureau of Local Roads & Streets SPECIAL PROVISION FOR LOCAL QUALITY ASSURANCE/ QUALITY MANAGEMENT QC/QA Effective: January 1, 2022

Replace the first five paragraphs of Article 1030.06 of the Standard Specifications with the following:

"**1030.06 Quality Management Program.** The Quality Management Program (QMP) will be Quality Control / Quality Assurance (QC/QA) according to the following."

Delete Article 1030.06(d)(1) of the Standard Specifications.

Revise Article 1030.09(g)(3) of the Standard Specifications to read:

"(3) If core testing is the density verification method, the Contractor shall provide personnel and equipment to collect density verification cores for the Engineer. Core locations will be determined by the Engineer following the document "Hot-Mix Asphalt QC/QA Procedure for Determining Random Density Locations" at density verification intervals defined in Article 1030.09(b). After the Engineer identifies a density verification location and prior to opening to traffic, the Contractor shall cut a 4 in. (100 mm) diameter core. With the approval of the Engineer, the cores may be cut at a later time."

Revise Article 1030.09(h)(2) of the Standard Specifications to read:

"(2) After final rolling and prior to paving subsequent lifts, the Engineer will identify the random density verification test locations. Cores or nuclear density gauge testing will be used for density verification. The method used for density verification will be as selected below.

	Density Verification Method
	Cores
X	Nuclear Density Gauge (Correlated when paving ≥ 3,000 tons per mixture)

Density verification test locations will be determined according to the document "Hot-Mix Asphalt QC/QA Procedure for Determining Random Density Locations". The density testing interval for paving wider than or equal to 3 ft (1 m) will be 0.5 miles (800 m) for lift thicknesses of 3 in. (75 mm) or less and 0.2 miles (320 m) for lift thicknesses greater than 3 in. (75 mm). The density testing interval for paving less than 3 ft (1 m) wide will be 1 mile (1,600 m). If a day's paving will be less than the prescribed density testing interval, the length of the day's paving will be the interval for that day. The density testing interval for mixtures used for patching will be 50 patches with a minimum of one test per mixture per project.

If core testing is the density verification method, the Engineer will witness the Contractor coring, and secure and take possession of all density samples at the

density verification locations. The Engineer will test the cores collected by the Contractor for density according to Illinois Modified AASHTO T 166 or AASHTO T 275.

If nuclear density gauge testing is the density verification method, the Engineer will conduct nuclear density gauge tests. The Engineer will follow the density testing procedure detailed in the document "Illinois Modified ASTM D 2950, Standard Test Method for Density of Bituminous Concrete In-Place by Nuclear Method".

A density verification test will be the result of a single core or the average of the nuclear density tests at one location. The results of each density test must be within acceptable limits. The Engineer will promptly notify the Contractor of observed deficiencies."

Revise the seventh paragraph and all subsequent paragraphs in Section D. of the document "Hot-Mix Asphalt QC/QA Initial Daily Plant and Random Samples" to read:

"Mixtures shall be sampled from the truck at the plant by the Contractor following the same procedure used to collect QC mixture samples (Section A). This process will be witnessed by the Engineer who will take custody of the verification sample. Each sample bag with a verification mixture sample will be secured by the Engineer using a locking ID tag. Sample boxes containing the verification mixture sample will be sealed/taped by the Engineer using a security ID label."

State of Illinois DEPARTMENT OF TRANSPORTATION Bureau of Local Roads & Streets

SPECIAL PROVISION FOR EMULSIFIED ASPHALTS

Effective: January 1, 2007 Revised: February 7, 2008

All references to Sections and Articles in this Special Provision shall be construed to mean specific Sections and Articles in the Standard Specifications for Road and Bridge Construction adopted by the Department of Transportation.

Replace the table after Note 2 in Article 403.02 with the following:

	Bituminous Materials Recommended for Weather Conditions Indicated						
Type of Construction	Warm [15 °C to 30 °C]* [(60 °F to 85 °F)]*	Hot [30 °C Plus]* [(85 °F Plus)]*					
Prime	MC-30, PEP	MC-30, PEP					
Cover Coat and Seal Coat	RS-2, CRS-2, RC-800, RC-3000, MC-800, MC-3000, SC-3000, HFE-90, HFE-150, HFE-300, HFRS-2, PEA**	RS-2, CRS-2, RC-800, RC-3000, MC-800, MC-3000, SC-3000, PG46-28, PG52-28, HFE-90, HFE-150, HFE-300, HFRS-2, PEA**					

* Temperature of the air in the shade at the time of application.

** PEA is only allowed on roads with low traffic volumes

Replace the table after Note 2 in Article 406.02 with the following:

Type of Construction	Bituminous Materials Recommended
Prime (tack) on Brick, Concrete, or Bituminous Bases (Note 3)	SS-1, SS-1h, CSS-1, CSS-1h, HFE-90, RC-70
Prime on Aggregate Bases (Note 4)	MC-30, PEP
Mixture for Cracks, Joints, and Flangeways	PG58-22, PG64-22

- Note 3. When emulsified asphalts are used, they shall be diluted with an equal volume of potable water. HFE emulsions shall be diluted by the manufacturer. The diluted material shall be thoroughly agitated within 24 hours of application and show no separation of water and emulsion. The diluted material shall not be returned to an approved emulsion storage tank.
- Note 4. Preparation of the bituminous PEP shall be as specified in Article 403.05.

Replace the table in Article 1032.04 with the following:

Spr	aying Application Temperature Ra	anges		
Turne and Grade of	Temperature Ranges			
Type and Grade of Bituminous Material	°F	O°		
Biturninous Materiai	min max.	min max.		
PEP	60 - 130	15 - 55		
PEA	140 - 190	60 -88		
MC-30	85 - 190	30 - 90		
MC-70, RC-70, SC-70	120 - 225	50 - 105		
MC-250, SC-250	165 - 270	75 - 130		
MC-800, SC-800	200 - 305	95 - 150		
MC-3000, SC-3000	230 - 345	110 - 175		
PG46-28	275 - 385	135 - 195		
PG52-28	285 - 395	140 - 200		
RS-2, CRS-2	110 - 160	45 - 70		
SS-1, SS-1h, CSS-1, CSS-1h	75 - 130	25 - 55		
SS-1hP, CSS-1hP	75 - 130	25 - 55		
HFE-90, HFE-150, HFE-300	150 - 180	65 - 80		
HFP, CRSP, HFRS-2	150 - 180	65 - 80		
E-2	85 - 190	30 - 90		
E-3	120 - 225	50 - 105		
E-4	165 - 270	75 - 130		

Add subparagraph (g) to Article 1032.06:

(g) Penetrating Emulsified Asphalt (PEA). The penetrating emulsified asphalt shall meet the following requirements when tested according to AASHTO T59:


Viscosity, Saybolt Fural @ 25°C (77°F),	sec:	20 - 500
Sieve Test, retained on 850 µm (No. 20) sieve, maximum,	%:	0.10
Storage Stability Test, 1 day, maximum,	%:	1
Float Test @ 60°C (140°F), minimum,	sec:	150
Stone Coating Test, 3 minutes,	:	Stone Coated Thoroughly
Particle Charge	:	Negative
pH, minimum	:	7.3
Distillation Test:		
Distillation to 260°C (500°F) Residue, minimum	%:	65
Oil Distillate by Volume, maximum	%:	3
Test on residue from distillation:		
Penetration @ 25°C (77°F), 100 g, 5 sec, minimum	dmm:	300

Replace the last sentence and table of Article 1032.06 with the following:

The different grades are, in general, used for the following.

Grade	Use
SS-1, SS-1h, CSS-1, CSS-1h, HFE 90, SS-1hP, CSS-1hP	Tack or fog seal
PEP	Bituminous surface treatment prime
RS-2, HFE 90, HFE 150, HFE 300, CRSP, HFP, CRS-2, HFRS-2, PEA	Bituminous surface treatment
CSS-1h Latex Modified	Microsurfacing

WASHINGTON ROAD DISTRICT TWP. 26 N., R 2 & 3W, 3rd P.M. 25-19000-01-GM (N-MFT) <u>TR 15D / Guth Rd</u>




Page 28 TR 21 / Irish Lane

Tazewell County Washington R.D. 25-19000-01-GM (N-MFT)

QUANTITIES

<u>Route/Section</u> TR 21 / Irish Lane TR 15D / Guth Rd	<u>Length (ft)</u> 7,875 <u>7,875</u> 15,750 LF	<u>Width (ft)</u> 20 20	<u>Area (SY)</u> 17,500 <u>17,500</u> 35,000 SQYD	
<u>Hot Mix Asphalt Surfac</u> 50' Each End	e Removal - Butt Jo	<u>pint</u>	444	SQYD
Polymerized Bituminou 0.72 lbs/SQYD on Existi			50,400	POUND
Hot-Mix Asphalt Surface 1.5" Thickness @ Cente		<u>1ix "C", N30:</u>	2,940	ΤΟΝ
Hot-Mix Asphalt Binde 0.5" Thickness @ Cente *Variences of Existing P	rline	<u>0:</u>	1,470	TON
Incidental Hot-Mix Asp 1370 LF x 1' Width x 2" *Mailboxes & Driveway	Thickness		17	TON
Traffic Control and Pro	tection Spl:		1	L SUM

TYPICAL CROSS SECTION TR 21 / Irish Lane ; TR 15D / Guth Rd




EXISTING AGGREGATE BASE -

Location: TF	R 21 / Irish Lane ;	TR 15D Guth Rd
Mixture Uses:	Binder Course	Surface Course
PG:	PG 58-28	PG 58-28
Design Air Voids:	4.0 @ N30	4.0 @ N30
Mixture Composition: (Gradation Mixture)	IL 9.5	IL 9.5
Friction Aggregate:		Mixture C


WASHINGTON ROAD DISTRICT Section: 25-19000-01-GM(N-MFT) Route: TR 21 Irish Lane ; TR 15D / Guth Rd Pleasant View Rd Easterly to Dee-Mack Rd

Washington R.D. SEC. 25-19000-01-GM(N-MFT)

STANDARD FOR HOT-MIX ASPHALT SURFACING AT SIDEROADS, ENTRANCES AND MAILBOXES




Notes: 1. Dimensions are approximate and may be adjusted in the field by the Engineer



CASE 1 : WITH HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING)

	I	AFER RAIES		
SPECIAL NOTE	ELEMENT	MAINLINE INTERSTATES &	ALL	1
NUMBER		4-LANE EXPRESSWAYS	OTHERS	
1	BUTT JOINT	1:480	1:240	2
	TAPER RATE			
2	TEMPORARY RAMP	1:80	1:40	
	TAPER RATE			3

TABLE A TAPER RATES



CASE 2 : NO HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING)

01-01-97	RENUM. C-23.01, NEW REVISION BOX	T.P.	08-21-13	MAJOR MODIFICATIONS	R.D.			
04-01-97	CORRECTION TO DEPTH	J.A.	04-12-16	MINOR CORRECTIONS	R.D.	STATE OF ILLINOIS	BUTT J	JOINTS
09-15-05	REVISED DESIGNER NOTE	M.M.A.	02-14-17	ADDED NOTE 5	R.D.	DEPARTMENT OF TRANSPORTATION		
10-16-06	REVISED TO 2007 SPEC.	M.A.	07-16-19	Wording and Spelling corrections	R.D.	Page 32	NOT TO SCALE	
								-

GENERAL NOTES

1. The work shall be done in accordance with Article 406.08 and the Special Provision for Butt Joints.

2. The pavement surface to be removed may be either bituminous or P.C. concrete. The work shall be performed in accordance with Article 440.04 and the Special Provisions for Butt Joints.


3. The saw cut joints shall be primed just prior to the placing of bituminous material. The work will be in accordance with the applicable portions of Article 406.05.

4. The length of butt joint is based on the taper rate times change in cold milling depth within the butt joint pay limits, unless otherwise indicated.


5. Temporary ramps are paid for separately and not included in the cost of the butt joints.

All dimensions are in inches (millimeters) unless otherwise noted.

	F.A. RTE.	SEC	LION	COUNTY	TOTAL SHEETS	SHEET NO.
TS						
SHT. 1 OF 3				CONTRACT	NO.	
CADD STD. 406101-D4	FED. RO	DAD DIST. NO.	ILLINOIS FED. A	ID PROJECT		




CASE 3 : HOT MIX ASPHALT SURFACE REMOVAL (COLD MILLING) TIE-IN TO EXISTING BITUMINOUS TAPER



					F.A. RTF.	SECTION	COUNTY	TOTAL SHEET
	STATE OF ILLINOIS		BUTT JOINTS	-				
	DEPARTMENT OF TRANSPORTATION			SHT. 2 OF 3			CONTRACT	NO.
	Page 33	NOT TO SCALE		CADD STD. 406101-D4	FED. ROAD DIST	. NO. ILLINOIS FED. /	AID PROJECT	


All dimensions are in inches (millimeters) unless otherwise noted.




Prop. Hot Mix Asphalt surf. removal (cold milling) per plans.

All dimensions are in inches (millimeters) unless otherwise noted.


			F.A. RTE.		SEC	TION	COUNTY	TOTAL SHEETS	SHEET NO.
NTS									
	C 4 D D	SHT. 3 OF 3					CONTRACT	NO.	
	CADD	STD. 406101-D4	FED. RO	DAD DIST. N	10.	ILLINOIS FED. A	ID PROJECT		




SIONS
rs sign
ee with
٠
WORKERS'



SIONS	
rs sign	OFF-RD MOVING OPERATIONS,
ee with	2L, 2W, DAY ONLY
•	
WORKERS'	
	STANDARD 701011–04



IONS
acing in taper.
gn.



	 _	
	 _	
•	ONE LANE	


SIGN S	PACING
Posted Speed	Sign Spacing
55	500′ (150 m)
50-45	350′ (100 m)
<45	200′(60 m)
143	200 (00 11)


All dimensions are in inches (millimeters)

SIONS	
r sign.	
+0	
).	

LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS


STANDARD 701301–04





SIONS
y Rumble
arricade notes
arning light on
s to top center.

(Sheet 1 of 3)







G20-I104(0)-6036

G20-I105(0)-6024


This signing is required for all projects 2 miles (3200 m) or more in length.

ROAD CONSTRUCTION NEXT X MILES sign shall be placed 500' (150 m) in advance of project limits.

END CONSTRUCTION sign shall be erected at the end of the job unless another job is within 2 miles (3200 m).

Dual sign displays shall be utilized on multilane highways.

WORK LIMIT SIGNING



Sign assembly as shown on Standards or as allowed by District Operations.



G20-I103-6036

This sign shall be used when the above sign assembly is used.


HIGHWAY CONSTRUCTION SPEED ZONE SIGNS

**** R10-I108p shall only be used along roadways under the juristiction of the State.

TRAFFIC CONTROL DEVICES

(Sheet 2 of 3)


STANDARD 701901-10



TRAFFIC CONTROL DEVICES

(Sheet 3 of 3)

STANDARD 701901-10



GENERAL NOTES

Type III Barricades and R11-2-4830 signs shall be positioned as shown in "Road Closed To All Traffic" detail on Highway Standard 701901.

Two Type A Low Intensity Flashing Lights shall be used on each approach in advance of the work area during hours of darkness. One light shall be installed above the barricades and the other above the first advance warning sign.

All warning signs shall have minimum dimensions of 36×36 (900 \times 900) and have a black legend on an orange reflectorized background.

When fluorescent signs are used, orange flags are not required.

Longitudinal dimensions may be adjusted to fit field conditions.

When the distance between the barricade and the intersection is between 1500' (450 m) and 2000' (600 m), the advance sign shall be placed at the intersection. When the distance between the barricade and the intersection is over 2000' (600 m), an additional sign shall be placed at the intersection. The additional sign shall give the distance to the barricade in miles or fractions of a mile.

All dimensions are in inches (millimeters) unless otherwise shown.

ISIONS	TYPICAL APPLICATION OF
tes from	TRAFFIC CONTROL DEVICES
S.	FOR CONSTRUCTION ON
	RURAL LOCAL HIGHWAYS
to	
•	STANDARD B.L.R. 21-9